



3 Pigeon Mountain Rd, Half Moon Bay
Western Boundary Wall
Preliminary Design and Groundwater
Drawdown Assessment Report

Document Number: J00538AB

Revision: Rev3

Prepared For: HND HMB Ltd

Date of Issue: 3 May 2024

Table of Contents

- Executive Summary** 1
- 1. Introduction 2
- 2. Geotechnical Investigations..... 3
 - 2.1 Regional Geology 3
 - 2.2 Existing Geotechnical Investigations..... 3
- 3. Design Soil Parameters and Ground Water Monitoring 4
- 4. Proposed Western Boundary Wall Analysis and Design..... 5
 - 4.1 Existing Western Boundary Timber Retaining Wall 5
 - 4.2 Modelled Construction Sequences..... 7
 - 4.3 PLAXIS Model Soil Parameters 9
 - 4.4 Retaining Wall Analyses Results..... 9
 - 4.4.1 Ground Settlement..... 9
 - 4.4.2 Wall Lateral Deflection 10
 - 4.4.3 Internal Forces Results 10
 - 4.4.4 Factor of Safety Analysis Results..... 11
- 5. Design..... 13
- 6. Groundwater Drawdown and Excavation Effect on Nearby Structures 14
 - 6.1 Settlement Prediction within Neighbouring Properties 14
 - 6.1.1 Settlement of structures 15
 - 6.1.2 Settlement of Public Services..... 16
 - 6.2 Groundwater Discharge Rate..... 17
- 7. Monitoring and Contingency Plan..... 18
- 8. Conclusion 20



Executive Summary

HND HMB Ltd has engaged Total Ground Engineering (TGE) to conduct geotechnical design of the western boundary retaining wall in support of a residential development at 3 Pigeon Mountain Road, which comprises 87 terrace houses.

TGE carried out the initial investigation between 15 and 16 June 2022, which involved eight hand augers and two standpipe piezometer groundwater monitoring wells for the resource consent application. Furthermore, we have also completed the second investigation on 23 August 2023, which comprised two additional piezometers and carried out the groundwater monitoring as requested in the queries from Auckland Council.

We have interpreted the existing and additional investigation data in conjunction with the information provided on the existing timber retaining wall to design the proposed western boundary retaining wall.

This design report has been updated in accordance with the updated architectural plan and civil work plan (updated on 08th April 2024 and 10th April 2024 respectively) and also integrated with the groundwater drawdown analysis. The preliminary design drawings are provided for the resource consent application. A detailed calculation set of predicted deformation at the surrounding structures are also included for supporting WAT 60423590 application. The pile levels and set-out needs to be confirmed in the detailed design stage with an accurate survey of the existing timber retaining wall.

1. Introduction

Total Ground Engineering (TGE) has been engaged by HND HMB Ltd to conduct geotechnical analysis and preliminary design of the western boundary wall at 3 Pigeon Mountain Road, Half Moon Bay. The site, legally described as Lot 1 DP 212125, is trapezoidal in shape covering an area of 1.4073 hectares. The site is located at the intersection of Compass Point Way and Pigeon Mountain Road.

The proposed development includes 87 terrace houses. A site plan of the development is shown in Figure 1.



Figure 1, Development Plan by ASC Architect updated on 08 April 2024.

We have referred to the following updated documents for design and :

- 3 Pigeon Mountain Road – S92 Response Architecture Design by ASC architects, dated 08 April 2024.
- 3 Pigeon Mountain Road Proposed Earthwork Plan by Airey Consultant, 10 April 2024. The cut levels for the building platforms of Lot 85 – 88 along the western boundary retaining wall is increased by 0.5 m and the maximum retaining height is reduced from 5.0 m to 4.5 m.
- 3 Pigeon Mountain Property File from Auckland Council including the existing western boundary retaining wall details.
- 3 Pigeon Mountain Road WAT60423590 application queries from Auckland Council received on 17 November 2023 and 1 December 2023.

During the resource consent review process, we have installed two additional piezometers in the proposed deepest excavation area and carried out the groundwater monitoring as requested in the RC RFI. Based on the monitoring results, the proposed excavation plan indicates a relatively shallow but permanent groundwater drawdown along the western

boundary wall.

During the WAT60423590 application review process, we have added the calculation details of the predicted settlement at the surrounding structures and updated the monitoring scheme in this report.

This report includes the updated geotechnical investigation, updated groundwater monitoring results, updated retaining wall analysis with preliminary design and updated groundwater drawdown assessment for supporting the resource consent and water permit application.

The key provided documents are enclosed in Appendix A.

2. Geotechnical Investigations

2.1 Regional Geology

Reference has been made to the New Zealand Geology Web Map on the GNS website, <http://data.gns.cri.nz/geology/>, accessed on 10th June 2022 (refer Figure 2). The maps indicate that the site is underlain by Tuff of the Auckland Volcanic Field (AVF, coloured purple in Figure 2). The AVF tuff comprises comminuted pre-volcanic materials with basaltic fragments, and unconsolidated ash and lapilli deposits. These volcanic materials can be spatially variable in terms of material types, often with an abrupt end to ash deposits, with well sorted lapilli, tuff, ash and breccia at the margins.

The map indicates a geological boundary to the north of the site, mapped as East Coast Bays Formation (ECBF, coloured orange in Figure 2) of the Waitemata Group. The ECBF comprises alternating sandstone and mudstone with variable volcanic content and interbedded volcanoclastic grit beds.

The ECBF typically weathers at the surface forming stiff to very stiff silts and clays which can contain reactive clay mineralogy and be prone to shrinking and swelling due to varying moisture content conditions.



Figure 2. Site Geology Map

2.2 Existing Geotechnical Investigations.

The geotechnical findings by TGE’s first investigation on 15th-16th Jun 2022 and second

investigation on 23 August 2023 are consistent with the published Auckland Geomap and Aurecon's initial findings. We have attached the extracts from TGE report "J00538AA Geotechnical Investigation Report_r0" and the two additional hand auger logs (HA09&HA10) in Appendix A.

3. Design Soil Parameters and Ground Water Monitoring

Based on the available data and our experience in the above materials, we have adopted the following soil parameters for retaining wall design:

Table 1. Adopted Soil Properties.

	Unit Weight (kN/m ³)	Cohesion c(kPa)	Internal Friction Angles (degrees)	Undrained Shear Strength (kPa)
Existing Fill	17	7	32	70
Puketoka Formation	17	3	30	50
Completely weathered – Highly weathered ECBF	17	7	32	100
Moderately – Slightly Weathered ECBF	18	20	38	400

During TGE's investigation and monitoring from 16 June 2022 to 31 January 2024, we have measured the groundwater in monitoring piezometers HA01, HA07, HA09 and HA10. The groundwater measurement data is updated in Table 2.

The measurements indicate the groundwater level has increased dramatically from -4.9 m at HA01 to -1.4 m during the 2023 Auckland Anniversary Weekend Flood Event and Cyclone Gabrielle. Subsequently, the groundwater level fluctuates around -1.4 m over the winter period and decreases to -2.5 to -4.0 m over the dry summer period. We have referred to the updated earthwork plan showing that the proposed excavation along the western wall is below the averaged water table. The excavation plan indicates a permanent groundwater drawdown ranging from 0.1 – 2.0 m along the western boundary wall.

Table 2. Ground Water Monitoring Measurements (updated to 20 February 2024)

Monitoring Dates and Levels (below ground level, m)				
Piezo Location	16/06/2022 (Installation day)	22/02/2023	22/03/2023	5/04/2023
HA01	4.9	1.4	2.4	3.0
HA07	3.7	2.1	2.7	2.0
Piezo Location	23/08/2023 (installation day)	25/08/2023	1/09/2023	11/09/2023
HA01	/	1.72	1.52	1.50
HA07	Removed			
HA09	1.42	1.58	1.37	1.44
HA10	1.35	1.49	1.32	1.27
Piezo Location	17/01/2024	31/01/2024	20/02/2024	
HA01	2.71	3.27	3.88	
HA09	1.90	2.05	2.28	
HA10	1.66	1.74	1.98	

4. Proposed Western Boundary Wall Analysis and Design

4.1 Existing Western Boundary Timber Retaining Wall

The aerial photo (circa 2006) shown in Figure 3 from Auckland Geomaps indicates that the wall was constructed at about the same time as the school.



Figure 3. Aerial Photo from Auckland Council (2006)

We have reviewed the existing survey conducted by Envivo and the property file information related to the timber retaining wall. The retained height of the existing timber wall ranges from approx. 0.5 m to 2.8 m as shown in Figure 4:




Figure 4 Existing Timber Retaining Wall Design Long Section from Property File (2002)

We have visited the site and carried out measurements of the existing timber retaining wall dimensions including pole size and pole spacing. The provided retaining wall design information indicates the cantilevered height to embedment depth ratio of the existing timber retaining wall is approximate 1:1 which was normally acceptable at that time.

We have tabulated the existing levels and the design finished floor levels with a 550 mm reduction to finished ground levels along the western boundary retaining wall as shown in below Table 3 , extracted from Appendix B.

Table 3. Western Boundary Existing Timber Retaining Wall Information.

Western Boundary Existing Retaining Wall Information updated 2024.04.10												
Existing Timber Retaining Wall Top Level (From North to South)	Existing Toe Level	Design Finished Floor Levels	550 mm Sub Excavation Levels	Proposed Excavation Depth (m)	Approximate Groundwater Drawdown Depth (m) (1.4 m bgl interpreted)	Existing Retaining Height (m)	Proposed Design RH (m)	Representative Design RH Range (m)	Covering Lot No #	Deepest Excavation Spot	Nearest corresponding piezo. No	Analysed Section
/	/	/	/	/	/	No EXTG. Retaining Wall	/	/	Lot #1	Fill-up areas without retaining wall		
12.48	11.22	9.71	9.16	2.1	0.7	1.26	3.32	3.0 - 4.5	Lot # 88	Lot 88 Southwestern Corner	HA09	Section 1
13.56	12.78	10.70	10.15	2.6	1.2	0.78	3.41					
14.48	13.51	10.70	10.15	3.4	2.0	0.97	4.33					
16.13	15.09	12.20	11.65	3.4	2.0	1.04	4.48					
16.29	15.28	13.20	12.65	2.6	1.2	1.01	3.64	3.5 - 4.5	Lot # 83 - 86	Lot 85 Southwestern Corner		Section 2
16.84	15.79	13.20	12.65	3.1	1.7	1.05	4.19					
18.40	16.77	14.70	14.15	2.6	1.2	1.64	4.25	4.0 - 4.5	Lot # 79 - 82	Lot 79 Southwestern Corner	HA10	Section 3
18.62	17.67	14.70	14.15	3.5	2.1	0.95	4.47					
19.05	18.01	15.10	14.55	3.5	2.1	1.04	4.50					
18.77	17.74	15.10	14.55	3.2	1.8	1.03	4.22					
19.27	17.87	16.60	16.05	1.8	0.4	1.40	3.22	3.0 - 3.5	Lot # 41- 42			
19.48	18.71	17.00	16.45	2.3	0.9	0.77	3.03					
19.70	17.98	17.00	16.45	1.5	0.1	1.73	3.25					

We have divided the wall into four representative retained height ranges as shown in Table 3 being the critical design sections. The extent of these design sections are shown in Figure 5. The maximum retained height of 4.5 m is beyond the limits of cantilevered timber poles in these soils and would generate ground deformations exceeding the limits commonly required in the resource consent conditions. Therefore, stiffer steel kingpost poles piles are required to minimise retaining wall deflections and settlement of any surrounding structures.




Figure 5. Retaining Wall Plan and Section Position overlying Civil work plan.

We have adopted the above Sections 1-3 for analysis of each retaining height range using the Finite Element software package PLAXIS 2D. Section 4 will adopt the same design as Section 1. The groundwater drawdown is also modelled and analysed to assess the structure deformations, ground settlements and retaining wall internal actions. Analysis of Section 3 with a maximum 4.5 m retained height is presented in detail below. Analysis outputs of the rest of the retaining walls are attached in Appendix C.

4.2 Modelled Construction Sequences.

The critical section for Section 3 as shown in Figure 5 is 4.5 m high and located at approximate wall chainage 46 (drawings included in Appendix D). We have used Plaxis 2D to model the geological profile and the phased construction of the proposed retaining wall. We have also imposed a 10 kPa surcharge to model the neighbouring property.

Figure 6 shows the general arrangement of the Plaxis model at the critical cantilevered phase.




Figure 6. Plaxis Model General Arrangement-Section 3.

The modelling sequence, replicating the proposed construction sequence is as follows:

Analyse Existing Conditions :

- Phase 0: Initial Phase (Initializing FEM model)
- Phase 1: Install Existing Timber Retaining Wall (school development)
- Phase 2: Neighbouring property construction (imposing line loads and add Point A-D for settlement prediction)

Analyse Proposed Wall Construction :

- Phase 3: Install proposed retaining wall
- Phase 4: Backfill between Existing and New Retaining Wall
- Phase 5: Excavate to finished level in front of the Wall (temporary 0.55 m below FFL)
 - Phase 5.1: Apply worst ground water scenario
 - Phase 5.2: Apply seismic scenario ($K_n = 0.19 g$)

To limit wall deflection and ground deformation, we have modelled a 250UC-89.5 for this critical retaining height range.

We have adopted the following configurations and specifications in the analysis model:

- The proposed retaining wall is positioned approximately 1.6 m from the western boundary and a constant 0.7m offset from existing timber retaining wall alignment to avoid clash.
- The proposed retaining wall is 1.0 m lower than the existing timber retaining wall as per architectural and urban design requirements.
- Existing timber retaining wall of 350 mm SED at 1.0 m c/c spacing with 10 kPa surcharge behind.
- 250UC-89.5 kg/m post at 1.0 m c/c. UC stiffness $EA = 2.280E+6$ kN/m run

- Maximum temporary retaining height is 4.5 m from the existing wall top level.
- Pile length 12.0 m and approximate Pile embedment 8.0 m below FFL .
- Groundwater level -1.4 m bgl (approx. R.L.15.9) and the drawdown to excavation level (550 mm below FFL, approx. R.L. 14.53).

4.3 PLAXIS Model Soil Parameters

For Plaxis analysis we have adopted Mohr-Coulomb soil parameters in general accordance with

Table 1 with additional stiffness and permeability parameters as shown in Table 4.

Table 4. Soil Parameters adopted in Plaxis Analyses

Parameters Soil Strata	Cohesion c (kPa)	Phi Φ (Degrees)	Stiffness E (MPa)	Poisson Ratio v	Permeability kv = kh (m/s)
Existing Fill	7	32	10	0.3	1.0 E-07
Puketoka Formation	3	30	7	0.3	1.0 E-07
Completely weathered – Highly weathered ECBF	7	32	15	0.3	1.0 E-07
Moderately – Slightly Weathered ECBF	20	38	50	0.3	1.0 E-08

4.4 Retaining Wall Analyses Results

4.4.1 Ground Settlement

The analyses indicate that maximum ground settlement immediately behind the wall is 16.7 mm occurring at Phase 5 as shown in Figure 7.




Figure 7. Phase 5 Settlement Contours.

The predicted settlements at the monitoring point A-B are -5.14 mm and -1.48 mm respectively (minus indicates settlements). We have also summarized the potential groundwater drawdown influence on the existing services and structures behind the wall and discuss these in the following chapter.

4.4.2 Wall Lateral Deflection

We have extracted wall deflection profiles at several important phases. Figure 8 shows a maximum lateral displacement of 16.7 mm after Phase 5. This deflection represents a ratio of wall-height upon deflection (H/d) of 270 which is acceptable.




Figure 8. Phase 5 Lateral Deflection.

The detailed wall analysis outputs for all of the sections are enclosed in Appendix C.

4.4.3 Internal Forces Results

Wall internal forces have been extracted from the analysis. The wall shear forces and bending moments at Phase 5 are shown in Figure 9 and Figure 10.




Figure 9. Shear Force Diagram- Phase 5.




Figure 10. Bending Moment Diagram- Phase 5.

The outputs for the rest of the walls are attached in Appendix C. All factored internal actions are less than the design capacity of the structural elements.

4.4.4 Factor of Safety Analysis Results

Table 5 shows the global stability criteria adopted in general accordance with Auckland Council’s Code of Practice for Land Development and Subdivision (v2.0), Section 2.6.8.

Table 5: Design Criteria

Loading Condition	Minimum Factor of safety (FS)
Normal Groundwater Condition	1.5
Worst Credible Groundwater	1.3
Pseudo-static seismic (ULS PGA)	1.0

We have carried out a global factor of safety analysis for both static and seismic cases for Phase 5. Figure 11 indicates the retaining wall provides a factor of safety 1.68 under static conditions exceeding the normally accepted minimum requirement 1.5 for the normal ground water scenario.



Figure 11. FoS under three design scenarios.

For the worst-case groundwater, we have increased the water level to R.L.17.4. This results in a factor of safety of FS = 1.65 as shown in Figure 11, exceeding the minimum requirement of 1.3.

The factor of safety (FoS) is 2.60 under a seismic horizontal acceleration 0.19 g as shown in Figure 11, exceeding the minimum requirement 1.0 suggested in the Auckland Council guidance for slope instability under seismic conditions.

We have summarised the key analysis results of Sections 1 to 3 and the design details in Table 6.

Table 6. Wall Analyses Summary.

Section No.	Retention Pile Size	c/c spacing (m)	Pile Length (m)	Modelled Retained Height (m)	Long-Term Factor of Safety (Normal Ground Water)	Short-Term Factor of Safety (Worst Ground Water)	Seismic Factor of Safety
Section 1	250 UC-89.5	1.0	12.0	4.33 (3.78 permanent)	1.66@ 0.4 m	1.56 @ 0.4 m	2.21 @ 0.4 m
Section 2	250 UC-89.5	1.0	12.0	4.48 (3.93 permanent)	1.85@ 0.4 m	1.83 @ 0.4 m	3.60 @ 0.4 m
Section 3	250 UC-89.5	1.0	12.0	4.50 (3.95 permanent)	1.68@ 0.4 m	1.65 @ 0.4 m	2.60ss @ 0.4 m

5. Design

Both short-term and long-term analyses are considered when determining the critical design actions for the structural member design. All structural elements have been designed in accordance with the NZS1170 – Design Actions suit of standards. The steel piles have been designed in accordance with NZS3404 “Steel Structures Standard” and timber lagging has been sized in accordance with NZS3603 “Timber Structures Standard”. An earth load factor of 1.5 has been adopted on all analysis output loads to give the Ultimate Limit State (ULS) design actions.

Wall Section 3 extracted from the drawings is shown in Figure 12. We have assumed a nominal maximum retained height of 4.5 m. The proposed retaining wall comprises 12.0 m long, 250UC89 steel piles encased in concrete at 1.0 m spacings. 150 x 50mm timber lagging supports the retained ground between the piles.




Figure 12; Typical Cross Section 3.

We have specified a minimum wall offset 700 mm to avoid clashes with the existing pile encasement which needs to be confirmed by detailed survey during the detailed design stage.

6. Groundwater Drawdown and Excavation Effect on Nearby Structures

We have undertaken further assessment and groundwater drawdown analyses to address the queries raised by Auckland Council on 11 August. The groundwater drawdown and associated aggregate settlements (mechanical plus consolidation) with the excavation are assessed using Plaxis 2D Flow Module.

The predicted settlements on the environment, adjacent buildings, structures and public services are discussed and summarized in following sections.

6.1 Settlement Prediction within Neighbouring Properties

In order to calculate the maximum predicted differential settlement under the house footprint as requested in WAT queries, we have extracted the information of interim points between A (house start point) and B (house end point) as shown in Figure 13. The settlement prediction of each point are summarised in Table 7.




Figure 13. Interim Points Numbering for Section 3.

Table 7. Interim points settlement results Summary.

Section 1 Model								
Point Name	B	1	2	3	4	5	6	A
Model Coordinates	(-18.7,14.48)	(-16.9,14.48)	(-14.9,14.48)	(-12.9,14.48)	(-10.8,14.48)	(-8.58,14.48)	(-6.2,14.48)	(-3.7,14.48)
Predicted settlement (mm)	-3.38	-3.46	-4.04	-4.83	-5.55	-6.08	-6.14	-5.50
Section 2 Model								
Point Name	B	1	2	3	4	5	6	A
Model Coordinates	(-23,16.13)	(-20.1,16.13)	(-17.3,16.13)	(-14.4,16.13)	(-11.6,16.13)	(-8.7,16.13)	(-5.89,16.13)	(-3,16.13)
Predicted settlement (mm)	-0.74	-1.07	-1.38	-1.72	-2.08	-2.48	-2.89	-3.37
Section 3 Model								
Point Name	B	1	2	3	4	5	6	A
Model Coordinates	(-19,19.05)	(-16.2,19.05)	(-13.6,19.05)	(-10.8,19.05)	(-8.07,19.05)	(-6.72,19.05)	(-5.37,19.05)	(-4,19.05)
Predicted settlement (mm)	-1.48	-2.0	-2.61	-3.34	-4.03	-4.35	-4.70	-5.14

On basis of the above settlement predictions, we have calculated the differential settlements of each point pairs and tabulated the maximum settlements in below Table 8:

Table 8. Maximum differential Settlement Summary.

Property Address (Compass Point Way)	Corresponding Nearest Analysed Section	Max. Settlement (mm)	Critical Point Pair	Settlement Difference (mm)	Point Pair Distance (m)	Maximum Differential Settlement Calculation
#76	Section 1	< -6.1	(2,3)	<0.78 *	2.01	0.78/2010 ≈ 1:2576
#78	Section 1	-6.1	(2,3)	0.78	2.01	< 0.78/2010 ≈ 1:2576
#80	Section 2	-3.37	(6,A)	0.48	2.89	0.22/2600 ≈ 1:6020
#82	Section 3	5.14	(6,A)	0.45	1.37	0.45/1370 ≈ 1:3044
#84	Section 3	< 5.14	(6,A)	< 0.45 *	1.37	< 0.45/1370 ≈ 1:3044

*: The maximum retaining heights at #76 and #84 are less than at #78 and #82 respectively. Thus the settlements are expected to less than the predicted settlement difference.

6.1.1 Settlement of structures

The maximum differential settlement gradient is approximately 1V:2576H (0.0388%) between Point 2 & 3 near Section 1 (CH60). We have compared the predicted settlements and the maximum differential settlement with widely used building damage assessment criteria in Table 9. The results indicate the description of the degree of damage is “Negligible”.

Table 9. Building Damage Assessment Criteria.

Building Damage Classification after Burland (1995), and Mair et al (1996)			Approx. equivalent ground settlement and slopes (after Rankin 1988)	
Category of Damage	Description of degree of damage	Limiting Tensile Strain %	Max. Slope of Ground	Max. Settlement of Building (mm)
0	Negligible	Less than 0.05		
1	Very Slight	0.05 to 0.075	Less than 1:500	Less than 10
2	Slight	0.075 to 0.15	1:500 to 1:200	10 to 50
3	Moderate	0.15 to 0.3	1:200 to 1:50	50 to 75
4	Severe	Greater than 0.3	1:200 to 1:50	Greater than 75
5	Very Severe		Greater than 1:50	Greater than 75

Although analysis indicates no significant adverse effects on the adjacent structures, we propose a detailed monitoring and contingency plan as a prudent measure during the construction. This is discussed further in the following sections in accordance with the review feedbacks from WAT application.

6.1.2 Settlement of Public Services

The provided civil cross sections indicate a public 150 mm wastewater sewer and a 300 mm stormwater sewer running through the backyard of neighbouring properties # 76 – 84 compass point way. We have tabulated the coordinates of service points in each analysed section as shown in Table 10.

Table 10. Monitoring Point Positions refer to Figure 6.

Points \ Relative Location	Section 1 (m)	Section 2 (m)	Section 3 (m)
Point C (WW Line)	(-3.47,12.68)	(-3.7,14.12)	(-3.6,17.36)
Point D (SW Line)	(-2.0,11.7)	(-2.1,13.17)	(-2.1,-17.0)

For the 150mm WW pipe, the analysis predicts 5.1 mm settlement as shown in Figure 14. Assuming that the 5.1 mm of settlement occurs over a transition length of 5 m to 8.5 m the gradient would range from 1:1000 to 1:1700. Adopting Rankine’s description of damage as shown in Table 9 would classify the effect as “Negligible”. to “Very Slight”.

For the 300 mm SW pipe, the analysis predicts 5.8 mm settlement as shown in Figure 15. Assuming that the 5.8 mm of settlement occurs over a transition length of 5 m to 8.5 m the gradient would range from 1:862 to 1:1465. Adopting Rankine’s description of damage as shown in Table 9 would classify the effect as “Negligible”. to “Very Slight”.




Figure 14. Predicted WW Line Settlement at Section 3.




Figure 15. Predicted SW Line Settlement at Section 3.

Section 3 is the critical section and the settlement prediction of the rest of the analysis sections are included in Appendix C and also tabulated in Table 11.

Table 11. Predicted Settlement after Phase 5.

Analysed Section	Modelled Temporary Retained Height (m)	Wall Static Lateral Deflection (mm)	Neighbouring Property Corner Distance to New Wall (m)	Predicted Settlement at wall-behind 150 WW line Point C (mm)	Predicted Settlement at wall-behind 300 SW line Point D(mm)
Section 1	4.33 (3.78 permanent)	13.4	3.6	-5.45	-4.66
Section 2	4.48 (3.93 permanent)	16.0	3.0	-3.22	-3.09
Section 3	4.50 (3.95 permanent)	16.7	4.0	-5.15	-5.81

6.2 Groundwater Discharge Rate

We have also estimated groundwater discharge rate over the excavation platform length of 10.0 m. Figure 16 shows the total discharge rate is 1.686E-3 m³/day per m run. The outputs for the rest sections are summarized in Table 12.



Figure 16. Long-term Groundwater Discharge Rates.

Table 12. Groundwater Discharge Rates Summary.

Analysed Section	Original GWL (mRL)	Change in Water Head(m)	Excavation Platform Length (m)	Long-term Discharge Rate (m ³ /day/m run)
Section 1	12.11	1.96	10.0	1.313E-3
Section 2	12.72	1.07	10.0	1.347E-3
Section 3	15.90	1.35	10.0	1.686E -3

The above analysis indicates that long-term groundwater flows are estimated as $1.686 \times 10^{-2} \text{ m}^3/\text{day}$, which is approximately 0.012 litres/min. This indicates a slow trickle of groundwater discharged for the subsoil drains.

7. Monitoring and Contingency Plan

To monitor the excavation and groundwater drawdown influence on the neighbouring property & public services, we proposed a schedule of horizontal deflection marks (DM1-9) at the top of the proposed retaining wall. DM 8 and DM 9 are placed on the existing timber retaining wall to monitor its deflection during the construction.

We have also planned a set of building settlement marks BS1-20 around the neighbouring properties to monitor the potential ground deformation and its differential settlements during the construction.



Figure 17. Updated Monitoring Plan.

Alert Level is commonly defined as the situation where monitoring reaches a level close to where damage may occur unless movement continues unchecked and requires review of available monitoring information (plus other information) to assess the future trend. Alarm Level is commonly defined as the situation where monitoring reaches a level where damage may occur and requires immediate action including the cessation of ground dewatering and other construction activities that may have an effect on ground deformation. Alert level is usually set as 70 % of Alarm level.

We have developed the following monitoring Table 13 to reflect the specific levels for each monitoring point:

Table 13. Monitoring Points Alert/ Alarm Level.

Monitoring Points	Alert Level (mm)	Alarm Level (mm)	Differential Settlement Alert Level	Differential Settlement Alarm Level	Monitoring Frequency
DM 1-3	11.7	16.7	/	/	Weekly
DM 4-5	11.2	16.0	/	/	Weekly
DM 6-7	9.4	13.4	/	/	Weekly
DM8-9	11.7	16.7	/	/	Weekly
BS1-20	7	10	1:700	1:500	Weekly

The monitoring frequency should be a minimum of weekly and at each 1.0 metre depth of excavation.

We propose the following actions as a consequence of monitoring points exceeding the alert or alarm levels.

- Alert level exceeded. Construction may continue and a report to be provided by the geotechnical engineer summarising the wall movements and recommending any remedial actions.
- Alarm level exceeded. Construction affecting the retaining wall to be paused while a report is provided by the geotechnical engineer summarising the wall movements and recommending any remedial actions.

We also recommend that a dilapidation/ condition survey of each of the neighbouring residential properties be carried out by a building surveyor or inspector following building consent approval and before any physical works onsite.

In order for the monitoring and contingencies to be clearly understood by all parties, we recommend that a stand-alone, concise, Monitoring and Contingency Plan be developed prior to the construction stage, to be followed by the Contractor during construction.

8. Conclusion

The proposed development includes 87 terrace houses. The site is underlain by Tuff of the Auckland Volcanic Field (AVF), Puketoka Formation and East Coast Bays Formation (ECBF) of the Waitemata Group. The site is within a residential area of Auckland with Half Moon Bay Marina to the north.

The design report have been updated in accordance with the revised architectural plan, updated civil work plan and also integrated with WAT queries. The proposed retaining wall should provide adequate factors of safety and capacity during the construction and restrain the wall deflection as well as ground settlement within the permitted limits. A preliminary monitoring and contingency plan have been provided for resource consent and water permit application.

We trust this letter meets your requirements. Please contact the undersigned if you have any questions.

Prepared by:



Bruce Li
Geotechnical Engineer
MEng, MSc, MICE, EPENZ
Total Ground Engineering

Reviewed and Authorised by:



Neil Jacka
Principal Geotechnical Engineer
BE(Hons), CMEngNZ, IntPE
Total Ground Engineering

Appendices

- Appendix A Reference Information
- Appendix B Provided Civil Topos and Cross Sections
- Appendix C Analysis Outputs and Design Calculations
- Appendix D Preliminary Design Drawings
- Appendix E Monitoring and Contingency Plan

Limitations

This report has been prepared by Total Ground Engineering for our client's use in accordance with the proposed development plan and agreed scope of work. Any use or reliance by any other person, to which Total Ground Engineering has not given its prior written consent, is at that person's own risk.

The findings, recommendations and comments presented in this report are based on common methods of site investigation. The site investigation has been undertaken at discrete locations and ground conditions away from these locations could vary.

Appendix A

Reference Information

updated Archi set on 08/04/2024
updated Civil set on 10/04/2024

HND HMB Limited

3 PIGEON MOUNTAIN ROAD

3 PIGEON MOUNTAIN ROAD, HALF MOON BAY

CONTAIN WITHIN THIS PACKAGE



LOCATION PLAN

RESOURCE CONSENT SHEET LIST		
Sheet Number	Sheet Name	Current Revision
RA0000	COVER PAGE	G
RA0052	SITE PLAN ANALYSIS	A
RA0053	SITE PLAN ANALYSIS	G
RA0080	EXISTING SITE PLAN	G
RA0100	PROPOSED SITE PLAN	G
RA0101	PROPOSED LOT LAYOUT	G
RA0103	PROPOSED PLATFORM LEVEL PLAN	G
RA0104	PROPOSED RETAINING WALL PLAN	G
RA0110	PLATFORM LEVEL 3D	G
RA0111	OVERALL SITE 3D	G
RA0120	PROPOSED WASTE COLLECTION PLAN	G
RA0150	PROPOSED BASEMENT FLOOR PLAN	G
RA0151	PROPOSED GROUND LEVEL FLOOR PLAN	G
RA0152	PROPOSED LEVEL 1 FLOOR PLAN	G
RA0153	PROPOSED ROOF PLAN	G
RA0155	PROPOSED DECK LEVELS	G
RA0200	SITE PLANNING AREA (BUILDING COVERAGE)	G
RA0201	SITE PLANNING AREA (IMPERVIOUS AREA)	G
RA0202	SITE PLANNING AREA (LANDSCAPED AREA)	G
RA0203	SITE PLANNING AREA (FRONT YARDS LANDSCAPE AREA)	G
RA0204	SITE PLANNING AREA (OUTDOOR LIVING AREAS)	G
RA0205	OUTLOOK PLANS (LEVEL 00)	G
RA0206	OUTLOOK PLANS (LEVEL 01)	G
RA1300	SITE ELEVATIONS - OVERALL	G
RA1301	BLOCK ELEVATIONS - BLOCK A	G
RA1302	BLOCK ELEVATIONS - BLOCK B	G
RA1303	BLOCK ELEVATIONS - BLOCK C	G
RA1304	BLOCK ELEVATIONS - BLOCK D	G
RA1305	BLOCK ELEVATIONS 1 - BLOCK E	G
RA1306	BLOCK ELEVATIONS 2 - BLOCK E	G
RA1307	BLOCK ELEVATIONS - BLOCK F	G
RA1308	BLOCK ELEVATIONS - BLOCK G	G
RA1309	BLOCK ELEVATIONS 1 - BLOCK H	G
RA1310	BLOCK ELEVATIONS 2 - BLOCK H	G
RA1311	BLOCK ELEVATIONS - BLOCK I	G
RA1312	BLOCK ELEVATIONS - BLOCK J	G
RA1313	BLOCK ELEVATIONS - BLOCK K	G
RA1314	BLOCK ELEVATIONS - BLOCK L	G
RA1316	ELEVATION - RETAINING WALL	G
RA1317	ELEVATION - RETAINING WALL	G
RA1318	ELEVATION - RETAINING WALL	G
RA1319	ELEVATION - RETAINING WALL	G
RA1320	AVERAGE GROUND LEVEL	G
RA1400	SITE SECTIONS - OVERALL	G

RESOURCE CONSENT SHEET LIST		
Sheet Number	Sheet Name	Current Revision
RA1401	SITE SECTIONS - WESTERN RETAINING WALL	G
RA1402	SITE SECTIONS - WESTERN RETAINING WALL	G
RA1700	SUN SHADING - SPRING EQUINOX	G
RA1701	SUN SHADING - SPRING EQUINOX	G
RA1702	SUN SHADING - SUMMER SOLSTICE	G
RA1703	SUN SHADING - SUMMER SOLSTICE	G
RA1704	SUN SHADING - WINTER SOLSTICE	G
RA1705	SUN SHADING - WINTER SOLSTICE	G
RA1706	SUN SHADING - SPRING EQUINOX	G
RA1707	SUN SHADING - SPRING EQUINOX	G
RA1900	HIRB DIAGRAM	A
RA1901	PLANNING SUMMARY	A
RA2000	PERSPECTIVE RENDER	G
RA2001	PERSPECTIVE RENDER	G
RA2002	PERSPECTIVE RENDER	G
RA2003	PERSPECTIVE RENDER	G
RA2004	PERSPECTIVE RENDER	G
RA2005	PERSPECTIVE RENDER	G
RA2006	PERSPECTIVE RENDER	G
RA2007	PERSPECTIVE RENDER	G
RA2008	PERSPECTIVE RENDER	G
RA2100	LOOK AND FEEL	A
RA2101	LOOK AND FEEL	A
RA3000	UNIT TYPOLOGY - TYPE A1 INT	G
RA3001	UNIT TYPOLOGY - TYPE A1 CORNER	G
RA3001.1	UNIT TYPOLOGY - TYPE A.1 CORNER	G
RA3002	UNIT TYPOLOGY - TYPE A2 INT	G
RA3003	UNIT TYPOLOGY - TYPE A2 CORNER	G
RA3004	UNIT TYPOLOGY - TYPE B1 INT	G
RA3005	UNIT TYPOLOGY - TYPE B1 CORNER	G
RA3006	UNIT TYPOLOGY - TYPE C1 CORNER	G
RA3007	UNIT TYPOLOGY - TYPE C1.1 CORNER	G
RA3008	UNIT TYPOLOGY - TYPE C2 INT	G
RA3009	UNIT TYPOLOGY - TYPE C2	G
RA3010	UNIT TYPOLOGY - TYPE C2.1 CORNER	G
RA3011	UNIT TYPOLOGY - TYPE C3 INT	G
RA3012	UNIT TYPOLOGY - TYPE C3 CORNER	G
RA3013	UNIT TYPOLOGY - TYPE D1 INT & CORNER	G
RA3014	UNIT TYPOLOGY - TYPE D2 CORNER	G
RA3015	UNIT TYPOLOGY - TYPE D3 CORNER	B
RA3016	UNIT TYPOLOGY - TYPE D4	G
RA3017	UNIT TYPOLOGY - TYPE E1	G
GRAND TOTAL: 86		

asc architects

17 MAIDSTONE STREET, PONSONBY, AUCKLAND 1021
 PO BOX 5736, AUCKLAND 1141, NEW ZEALAND
 p. +64 9 377 5332 w. www.ascarchitects.co.nz

S92 RESPONSE

PROJECT # : JOB NO. 22924


DATE:08/04/2024



Legend


- Site
- Major Retail and Commercial
- ↔ Primary Arterial Roads
- ↔ Secondary Arterial Roads
- ↔ Collector Roads
- 📍 Community/ Sports Amenities
- 📍 Education
- 🌳 Greenspace

S92 RESPONSE





S92 RESPONSE



HND HMB LTD

3 Pigeon Mountain Rd, Half Moon Bay

Resource Consent 2024

Job: 220571-1



AIREY CONSULTANTS LTD
TEL: (09) 534 6523 www.aireys.co.nz

TAKAPUNA BOTANY QUEENSTOWN

CLIENT:
HND HMB LTD

JOB TITLE:
**3 PIGEON MOUNTAIN ROAD
HALF MOON BAY**


NOTES:

REV	AMENDMENT	DATE	BY
6	WEST BDY RET WALL REVISED	10/04/2024	LP
5	LOT 2 BDY REV. DWG 208 ADDED	09/04/2024	LP
4	LOT 15 & 16 FPATH ADDED	30/03/2024	LP
3	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 REVISIONS	20/10/2023	LP

DRAWING STATUS:
FINAL

ISSUE PURPOSE:
RESOURCE CONSENT

DESIGN: SW
DRAWN: LP
CHECKED: RT
DATE: 22/05/23
SCALE: NTS @ A3
DO NOT SCALE FROM DRAWINGS
© Copyright 2021 Airey Consultants Ltd



DRAWING TITLE:
COVER SHEET

JOB No: 220571-1
SHEET No: 000
REV: 6

SHEET INDEX - RESOURCE CONSENT PLANS	
Sheet Number	Sheet Title
100	SITE PLAN - OVERALL 1:500
200	SITE PLAN - EARTHWORKS CUT-FILL 1:500
201a	SITE PLAN - SEDIMENT CONTROL & EARTHWORKS STAGE 1
201b	SITE PLAN - SEDIMENT CONTROL & EARTHWORKS STAGE 2
201c	SITE PLAN - SEDIMENT CONTROL & EARTHWORKS STAGE 3
201d	SITE PLAN - SEDIMENT CONTROL & EARTHWORKS STAGE 4
202	SITE PLAN - PROPOSED LEVELS 1:500
202a	SITE PLAN - PROPOSED LEVELS JOAL 1 1:250
202b	SITE PLAN - PROPOSED LEVELS JOAL 2 1:250
202c	SITE PLAN - PROPOSED LEVELS JOAL 3 1:250
203	RETAINING WALL ELEVATIONS - WEST BOUNDARY
204	RETAINING WALL ELEVATIONS - NORTH & EAST BOUNDARY
204a	RETAINING WALL ELEVATIONS - SOUTH BOUNDARY
205	CROSS-SECTIONS THROUGH SITE
206	CROSS-SECTIONS THROUGH WEST BDY RETAINING WALL
206a	CROSS-SECTIONS THROUGH WEST BDY RETAINING WALL
207	SITE PLAN - PROPOSED CONTOURS 1:500
208	SITE PLAN - RETAINING WALL ELEVATION CHAINAGES
210	SEDIMENT CONTROL DETAILS
211	STABILISED CONSTRUCTION ENTRANCE DETAIL
212	SEDIMENT CONTROL - CATCHPIT PROTECTION
213	SEDIMENT CONTROL - DEB DETAIL
220	RETAINING WALL ELEVATIONS
221	RETAINING WALL ELEVATIONS
222	RETAINING WALL ELEVATIONS

ACCESSWAY	
300	SITE PLAN - ACCESSWAY CHAINAGES 1:500
301	SITE PLAN - VEHICLE CROSSING 1:250
302	SITE PLAN - ACCESSWAY LOTS 32-34
303	SITE PLAN - ACCESSWAY LOTS 48-50
310	ACCESSWAY LONGSECTION JOAL 5 & 4
311	ACCESSWAY LONGSECTION JOAL 1 & 2, & 3
312	FOOTPATH LONGSECTION
313	ACCESSWAY CROSS-SECTIONS
314	ACCESSWAY CROSS-SECTIONS
315	ACCESSWAY CROSS-SECTIONS
316	PARKING SPACES LONGSECTIONS - LOTS 48-50
317	GARAGE LONGSECTIONS - LOT 32-34
318	GARAGE LONGSECTIONS - LOT 35-40
319	GARAGE LONGSECTIONS - LOT 24-31
320	STANDARD DETAILS - VEHICLE CROSSING & ACCESSWAY
321	STANDARD DETAILS - MOUNTABLE KERB, RAISED FOOTPATH
	DRAINAGE
400	SITE PLAN - STORMWATER 1:500
410	STORMWATER LONGSECTION 1 & 2
411	STORMWATER LONGSECTION 3 & 4
412	STORMWATER LONGSECTION 5, 6 & 7
500	SITE PLAN - WASTEWATER 1:500
510	WASTEWATER LONGSECTION 1 & 2
511	WASTEWATER LONGSECTION 3 & 4
512	WASTEWATER LONGSECTION 5 & 6
513	WASTEWATER LONGSECTION 7 & 8
520	SITE PLAN - WATER SUPPLY, SERVICES 1:500

OTHER CONSENTS REQUIRED:

ALL PROPOSED PUBLIC DRAINAGE REQUIRES ENGINEERING APPROVAL.

ALL PRIVATE DRAINAGE, DETENTION TANKS & RETAINING WALLS REQUIRE BUILDING CONSENT.

PROPOSED VEHICLE CROSSINGS REQUIRES VEHICLE CROSSING APPROVAL.

WATERCARE WORKS OVER APPROVAL REQUIRED FOR WORKS WITHIN 2m OF WATERCARE ASSETS

NOTES

ALL WORK TO BE CARRIED OUT TO AUCKLAND COUNCIL & WATERCARE SERVICES ENGINEERING STANDARDS & STAMPED APPROVED PLANS.

CONTRACTOR TO LOCATE ALL SERVICES PRIOR TO COMMENCEMENT OF WORK.

NO DEVIATION FROM THESE ENGINEERING PLANS WITHOUT PRIOR WRITTEN APPROVAL FROM THE DESIGN ENGINEER.

STORMWATER, WASTEWATER AND WATERMAIN CONNECTIONS SHALL BE INSTALLED BY AN AUCKLAND COUNCIL & WATERCARE SERVICES APPROVED LICENSED CONTRACTOR AT THE APPLICANTS EXPENSE.

CONTRACTOR TO CONFIRM ALL DIMENSIONS ON SITE.

BOTH CONTRACTORS AND CONSULTANTS ARE TO TAKE ALL NECESSARY CARE AND PRECAUTION AT THE CONSTRUCTION SITE TO AVOID ACCIDENT AND INJURY FROM FALLING INTO EXCAVATIONS, CRUSHING BY SUBSIDING EXCAVATIONS AND THE MOVEMENT OF PLANT AND MATERIALS ON THE SITE.

THE CONTRACTOR SHALL PROVIDE SAFETY SHIELD OR EQUIVALENT SAFETY MEASURES FOR WORKS AREA DEEPER THAN OR EQUAL TO 1.5m TO COMPLY WITH WORKSAFE NEW ZEALAND.

CONTOURS AND MEASUREMENTS HAVE BEEN PROVIDED FOR ENGINEERING PURPOSES ONLY AND SHOULD NOT BE USED FOR TOWN PLANNING PURPOSES.

PILOT ALL SERVICES AND EXISTING DRAINAGE LINES PRIOR TO INSTALLATION OF NEW DRAINAGE LINES.

ANY DRAINAGE LINES ENCOUNTERED ON SITE DURING CONSTRUCTION NOT SHOWN ON THE ENGINEERING PLANS MUST BE REFERRED TO THE DESIGN ENGINEER.

LEVELS IN TERMS OF LANDS & SURVEY DATUM 1946.

ALL PUBLIC WASTEWATER MANHOLES TO BE 1050Ø RC WITH 600Ø HINGED LID AND SAFETY GRILLE UNLESS SHOWN OTHERWISE.

ALL PUBLIC STORMWATER MANHOLES TO BE 1050Ø RC WITH 600Ø HINGED LID UNLESS SHOWN OTHERWISE.


ALL PRECAST CONCRETE WASTEWATER MANHOLES TO BE THICKWALLED (WITH A 25mm SACRIFICIAL LAYER) OR HAVE APPROVED PE/PVC LINING AS PER WATERCARE MATERIAL SUPPLY STANDARD 14.8.4(H).

ALL SW & WW CONNECTIONS TO BE 100Ø uPVC SN16 UNLESS SHOWN OTHERWISE.

ALL 100Ø WW LOT CONNECTIONS TO BE FACTORY WYE JUNCTIONS (SN16 RATING).

ALL 100Ø WW LOT CONNECTIONS TO BE INSTALLED AT MIN. 30° INCOMING ANGLE FROM HORIZONTAL (MAX. 60°) PER WW15. INSTALL PLAIN BEND AT END OF WYE JUNCTION IF NECESSARY.

J:\220571-1\3 Pigeon Mountain Rd\CAO\WORKING DRAWINGS\3 PIGEON MOUNTAIN RD 220571-1_EW_November 23_recover.dwg, 10/04/2024, 3:46:18 pm, DWG To PDF.pc3



76 Compass Point Way

78 Compass Point Way

80 Compass Point Way

82 Compass Point Way

84 Compass Point Way

COMPASS POINT WAY

EXISTING FOOTPATH

ARA-TAI

PROPOSED FOOTPATH
DETAILED DESIGN TO BE
CONFIRMED BY AUCKLAND
COUNCIL PARKS DEPARTMENT
AT EPA/ BC STAGE

Airey

CIVIL, STRUCTURAL AND FIRE ENGINEERS

AIREY CONSULTANTS LTD
TEL: (09) 534 6523 www.aireys.co.nz

TAKAPUNA BOTANY QUEENSTOWN

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD
HALF MOON BAY

NOTES:

5	LOT 2 BDY REVISED	09/04/2024	LP
4	LOT 15 & 16 FP PATH ADDED	30/03/2024	LP
3	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - LAYOUT REVISED	20/10/2023	LP
REV	AMENDMENT	DATE	BY

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN:	SW
DRAWN:	LP
CHECKED:	RT
DATE:	22/05/23
SCALE:	1:500 @ A3
DO NOT SCALE FROM DRAWINGS	
© Copyright 2021 Airey Consultants Ltd	

ORIGINAL SIZE:



DRAWING TITLE:

SITE PLAN
OVERALL

JOB No:	SHEET No:	REV:
220571-1	100	5

1
DP 212125
1.4073 ha

PIGEON MOUNTAIN ROAD

EXTG VEHICLE CROSSING
TO BE REMOVED & BERM
RE-INSTATED TO AT
STANDARDS

SITE PLAN

1:500



PROPOSED ACCESSWAY
TO DETAIL GD12 DWG 320

JOAL 5

JOAL 1

JOAL 2

JOAL 4

JOAL 3

185°03'10" 132.91

BLOCK I

BLOCK B

BLOCK A

BLOCK H

BLOCK G

BLOCK F

BLOCK E

BLOCK C

BLOCK D

BLOCK K

BLOCK J

8.70

5.50

95°03'20" 122.74

78°21' 10.00

31°40' 7.73

344°38' 8.19

112°53' 70.29

110°34' 31.44

140°55' 2.26



76 Compass Point Way

78 Compass Point Way

PROPOSED RETAINING WALL SEE ELEVATION DWG 203

80 Compass Point Way

EXTG TIMBER RETAINING WALL MAX HEIGHT 2.78m

82 Compass Point Way

84 Compass Point Way

SITE PLAN 1:500

COMPASS POINT WAY

PROPOSED RETAINING WALL SEE ELEVATION DWG 204

ARA-TAI

STRUCTURAL ROOT ZONE TBC

BLOCK C

PIGEON MOUNTAIN ROAD

Isopachs shown have been calculated from existing ground level to FFL

ELEVATIONS TABLE

NUMBER	MIN. ELEVATION	MAX. ELEVATION	COLOUR
1	-3.00	-2.00	Red
2	-2.00	-1.00	Orange
3	-1.00	0.00	Light Orange
4	0.00	1.00	Light Green
5	1.00	2.00	Green
6	2.00	3.00	Dark Green
7	3.00	4.00	Very Dark Green



CIVIL, STRUCTURAL AND FIRE ENGINEERS

AIREY CONSULTANTS LTD
TEL: (09) 534 6523 www.aireys.co.nz

TAKAPUNA BOTANY QUEENSTOWN

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD
HALF MOON BAY

NOTES:

1
DP 212125
1.4073 ha

EARTHWORKS AREA (within site):
14000m²
(NOTE: AREA BEHIND EXTG WEST BDY RETAINING WALL WILL NOT BE DISTURBED = 80m²)

EARTHWORKS VOLUMES (Total):
Cut = 4076m³
Fill = 6690m³
Net Fill = 2614m³

EARTHWORKS VOLUMES (Ara Tai Reserve): AREA=225m²
Cut = 19m³
Fill = 8m³
Net Cut = 11m³

EARTHWORKS VOLUMES (Pigeon Mt berm): AREA=245m²
Cut = 35m³
Fill = 0m³
Net Cut = 35m³

Volumes are from existing ground level to FFL (including topsoil, subgrade, concrete).

Note:
Earthworks volumes for consent only. Not to be used for tender purposes.

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN: SW

DRAWN: LP

CHECKED: RT


DATE: 22/05/23

SCALE: 1:500 @ A3

DO NOT SCALE FROM DRAWINGS

© Copyright 2021 Airey Consultants Ltd

ORIGINAL SIZE:



DRAWING TITLE:

SITE PLAN
EARTHWORKS

JOB No:

220571-1

SHEET No:

200

REV:

6

RETAINING WALLS:
FOR TYPE AND HEIGHT OF
PROPOSED WALLS REFER
ARCHITECTS PLAN RA0104

SEE SOUTH BDY
ELEVATION DWG 204a

SEE EAST BDY
ELEVATION
DWG 204

PROPOSED RETAINING WALL
SEE ELEVATION DWG 204

A:\220571-1\3 Pigeon Mountain Rd\CAO\WORKING DRAWINGS\3 PIGEON MOUNTAIN RD 220571-1 EW_November 23_recover.dwg, 10/04/2024 3:47:32 pm, DWG To PDF.pc3

17 November 2023

Campbell Brown Planning Limited
PO Box 147001
Ponsonby
Auckland 1144

Attention: Yujie Gao

Dear Yujie,

Resource consent application – Further information request

Application number(s):	WAT60423590
Applicant:	HND HMB Limited
Address:	3 Pigeon Mountain Road, Half Moon Bay
Proposed activity(s):	Groundwater diversion arising from earthworks proposed by application BUN60419132

This letter is a request for further information that will help me better understand your proposal, including its effect on the environment and the ways any adverse effects might be mitigated.

Requested information

1. Please provide the predicted maximum total settlement for each dwelling of the dwellings located at 76 to 84 Compass Point Way.
2. Please provide the calculations for the predicted maximum differential settlement for each dwelling of the dwellings at 76 to 84 Compass Point Way.
3. Clarification is required for the total number of Deflections marks.

Note: Seven markers are shown on the proposed retaining wall on the monitoring plan as DM1 to DM7. However, the trigger level Table in the report (page 18) indicates eight markers as DM1-8.

4. Specific alert and alarm trigger levels are required for the DM's - which reflect the predicted the wall deflection and 70% of the deflection e.g DM3 appears to be located in the vicinity of Section 3 where 12m long 750mm diameter RC piles at 1.5m c/c spacing are proposed hence the alert trigger level should be 70% of 21mm (see Table 8) i.e 15mm and the alarm trigger level should be 21mm. Please confirm.
5. Please confirm any monitoring required for the existing retaining walls located at the western boundary. If not, justification is required.

- Council would expect to see pre and post construction detailed condition surveys of the dwellings at 76 to 84 Compass Point Way and pre and post construction detailed condition CCTV of the 150mm diameter uPVC sewer pipe and the 300mm diameter concrete stormwater pipe in the rear gardens of 76 to 84 Compass Point Way. Please confirm.

Providing the information

Please provide this information in writing within 15 working days¹ (before 8 December 2023). If you will not be able to provide the information by that date, please contact me before then to arrange an alternative time. We will not work on your application any further until either you provide this information, or you state that you refuse to provide it.

Note: If you will require more than 15 working days to provide this further information, I will seek that you agree to an extension of time under [section 37](#) of the Resource Management Act 1991 (the RMA). This will enable appropriate time for me to undertake the necessary review of the information once provided.

Refusing to provide the information

If you refuse to provide the information, or if you do not submit the information to us within 15 days (or by another other agreed time), the RMA requires that we publicly notify your application.²

If this happens, you will be required to pay the notification fee of \$20,000 in full before we proceed with the notification of your application.³

Next steps

Once you have provided the requested information, I will review what you have provided to make sure it adequately addresses all of the points of this request.

In the application acceptance letter, I described the statutory timeframe for our decision on your application. The time for you to respond to this further information request will be excluded from this timeframe⁴. I will be able to give you an updated⁴ forecast on a decision date on request once you have provided the information requested above.

If you have any queries, please contact me at aaron@civilplan.co.nz and quote the application number above.

Yours sincerely,

Aaron Grey
Consultant Planner

¹ Section 92A(1) of the RMA

² Section 95C of the RMA

³ Section 36AAB(2) of the RMA

⁴ Section 88C(2) of the RMA

Geotechnical Reference Information
from J00538 AA Geotechnical Investigation Report
updated 22.09.2023



27C WAIPAREIRA AVENUE
HENDERSON

PH: 027 557 7234
njacka@tge.co.nz

PROJECT
3 PIGEON MOUNTAIN
HALF MOON BAY
AUCKLAND


DRAWING TITLE
INVESTIGATION PLAN

Date:	JUL 2022
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
B	22.09.2023	ISSUED FOR RC APPLICATION	BL
A	07.04.2022	ISSUED FOR INFORMATION	BL

Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	REV
SCALE	1:800	J00538	100	B



SECTION AA

Geologic Unit:

- Puketoka Formation
- Fill
- AVF
- CW-HW ECBF
- MW-SW ECBF
- Ground Water Level
- Material Interface

NOTES:

Locations of features approximate only
 Original sheet size A3
 Levels refer to provided survey data
 Survey information are based on the
 Auckland Geomaps



27C WAIPAREIRA AVENUE
 HENDERSON

PH: 027 557 7234
 njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN
 HALF MOON BAY
 AUCKLAND**

DRAWING TITLE
GEOLOGICAL SECTION AA


Date:	JUL 2022
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
B	22.09.2023	ISSUED FOR RC APPLICATION	BL
A	07.04.2022	ISSUED FOR INFORMATION	BL

Check all dimensions and levels on site before commencing construction.
 This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.


PAPER SIZE	A3	JOB No.	DWG No.	REV
SCALE	1:500	J00538	101	B

Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769285.17 N5916423.99 Shear Vane No: 2982
 Date Started: 15-Jun-22 Ground Conditions: Slightly sloping, Grass Calibration Factor: 1.571
 Date Finished: 15-Jun-22 Groundwater Level (m): Not Encountered (15-Jun-22) Calibration Date: 18-Sep-20




In-situ field testing in accordance with the following Standards:
 Scala Penetrometer Testing: NZS 4402:1988, Test 6.5.2, Dynamic Cone Penetrometer
 Shear Vane Testing: Guideline for Hand Held Shear Vane Test, NZGS, August 2001


Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769250.13 N5916486.75 Shear Vane No: 2982
 Date Started: 16-Jun-22 Ground Conditions: Near level, Grass Calibration Factor: 1.571
 Date Finished: 16-Jun-22 Groundwater Level (m): Not Encountered (16-Jun-22) Calibration Date: 18-Sep-20




Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769323.22 N5916452.24 Shear Vane No: 2982
 Date Started: 15-Jun-22 Ground Conditions: Near level, Grass Calibration Factor: 1.571
 Date Finished: 15-Jun-22 Groundwater Level (m): 3.0m (15-Jun-22) Calibration Date: 18-Sep-20



Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769362.55 N5916428.41 Shear Vane No: 2982
 Date Started: 15-Jun-22 Ground Conditions: Near level, Grass Calibration Factor: 1.571
 Date Finished: 15-Jun-22 Groundwater Level (m): Not Encountered (15-Jun-22) Calibration Date: 18-Sep-20




Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769315.7 N5916485.41 Shear Vane No: 2982
 Date Started: 16-Jun-22 Ground Conditions: Near level, Grass Calibration Factor: 1.571
 Date Finished: 16-Jun-22 Groundwater Level (m): Not Encountered (16-Jun-22) Calibration Date: 18-Sep-20




Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769355.93 N5916465.98 Shear Vane No: 2982
 Date Started: 16-Jun-22 Ground Conditions: Sloping, Grass Calibration Factor: 1.571
 Date Finished: 16-Jun-22 Groundwater Level (m): Not Encountered (16-Jun-22) Calibration Date: 18-Sep-20

Stratigraphy	Depth (m)	Graphic Log	Soil description in accordance with <i>Guideline for the Field Classification and Description of Soil and Rock for Engineering Purposes</i> , NZ Geotechnical Society Inc., 2005	Groundwater Level (m)	Depth (m)	In-situ Field Testing							
						Shear Strength (kPa)		Dynamic Cone (Scala) Penetrometer					
						Peak:	Remoulded:	Depth (m)	Scala Blow Count / 100mm				
FILL			SILT, minor fine to medium angular gravel, trace clay, dark brown, stiff, moist, non-plastic [FILL]										
	0.5		End of Augerhole 0.4m [GRAVEL OBSTRUCTION]		0.5								
	1.0				1.0								
	1.5				1.5								
	2.0				2.0								
	2.5				2.5								
	3.0				3.0								
	3.5				3.5								
	4.0				4.0								
	4.5				4.5								
	5.0				5.0								
						In-situ field testing in accordance with the following Standards:							
						Scala Penetrometer Testing: NZS 4402:1988, Test 6.5.2, Dynamic Cone Penetrometer							
						Shear Vane Testing: Guideline for Hand Held Shear Vane Test, NZGS, August 2001							

Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769333.95 N5916508.07 Shear Vane No: 2982
 Date Started: 16-Jun-22 Ground Conditions: Near level, Grass Calibration Factor: 1.571
 Date Finished: 16-Jun-22 Groundwater Level (m): Not Encountered (16-Jun-22) Calibration Date: 18-Sep-20



Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769257.06 N5916543.39 Shear Vane No: 2982
 Date Started: 16-Jun-22 Ground Conditions: Slightly sloping, Grass Calibration Factor: 1.571
 Date Finished: 16-Jun-22 Groundwater Level (m): 1.0m (16-June-22) Calibration Date: 18-Sep-20




Scala Penetrometer Testing

Date tested: 16-June-2022


Tested By: JH

Test ID	HA01	Cont...	HA02	HA03	HA04	Cont...	HA05	HA07	Cont...	
Test from (m)	5.0	7.0	5.0	5.0	5.0	7.0	5.0	5.0	7.0	
Depth (m)	Blows/100mm penetration									
0.1	1	20	3	5	3	17	1	1	16	
0.2	1	20+	5	6	3	16	2	2	18	
0.3	1		8	6	4	16	4	2	20	
0.4	3		9	8	5	17	5	4	20+	
0.5	4		12	8	6	17	6	3		
0.6	4		17	8	7	18	7	4		
0.7	4		20	10	9	17	8	5		
0.8	4		20+	10	8	17	9	7		
0.9	6			9	9	20	10	6		
1.0	6			9	9	20+	13	4		
1.1	6			15	9		13	5		
1.2	8			14	10		15	9		
1.3	7			14	9		18	7		
1.4	8			15	11		23	11		
1.5	10			15	13		20+	12		
1.6	12			18	13			13		
1.7	13			19	14			13		
1.8	15			20	14			15		
1.9	14			20+	14			14		
2.0	14				14			12		
Test depth (m)	7.0	7.2	5.8	6.9	7.0	8.0	6.5	7.0	7.4	

Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769249.41 N5916531.58 Shear Vane No: 2982
 Date Started: 23-Aug-23 Ground Conditions: Slightly sloping, Grass Calibration Factor: 1.790
 Date Finished: 23-Aug-23 Groundwater Level (m): 3.0m (23-Aug-23) [Piezo screen 1.0m-5.0m] Calibration Date: 18-Jan-23



Drill Type: 50mmØ Hand Auger Project No: J00538 Logged By: JH
 Drilled By: JH Coordinates: NZTM2000 E1769245.15 N5916467.04 Shear Vane No: 2982
 Date Started: 24-Aug-23 Ground Conditions: Slightly sloping, Grass Calibration Factor: 1.790
 Date Finished: 24-Aug-23 Groundwater Level (m): 4.0m (23-Aug-23) [Piezo screen 1.0m-5.0m] Calibration Date: 18-Jan-23



In-situ field testing in accordance with the following Standards:
 Scala Penetrometer Testing: NZS 4402:1988, Test 6.5.2, Dynamic Cone Penetrometer
 Shear Vane Testing: Guideline for Hand Held Shear Vane Test, NZGS, August 2001

Existing Western Boundary Retaining Wall Details from Provided Property File




ROAD CENTRE LINE SETOUT COORDINATES

POINTS	EASTING	NORTHING
IP1	312148.020	899623.458
IP2	312026.488	899444.200
IP3	311998.818	899426.863
IP4	311993.821	899417.224
IP5	311995.742	899435.062
IP6	311979.789	899442.787
IP7	311982.805	899483.134
IP8	311568.237	899483.313
IP9	311802.050	899516.089
IP10	311861.678	899528.123
IP11	311928.531	899535.684
IP12	311933.722	899544.245
IP13	311848.481	899512.214
IP14	311941.368	899534.386
IP15	311884.296	899538.514
IP16	311828.700	899505.244
IP17	311858.238	899501.402
IP18	311844.881	899503.238
IP19	311820.123	899507.727
IP20	311810.402	899508.454
IP21	311800.201	899517.208
IP22	311781.248	899504.003
IP23	311782.451	899508.865
IP24	311774.899	899482.300
IP25	311789.026	899494.291
IP26	311784.842	899525.231
IP27	311782.237	899463.52
IP28	311782.237	899483.674
IP29	311781.705	899508.288
IP30	311727.641	899505.282
IP31	311780.123	899498.147
IP32	311786.841	899488.613
IP33	311776.742	899484.104
IP34	311777.783	899484.427
IP35	311860.371	899478.283
IP36	311810.182	899472.707
IP37	311840.072	899470.082

RETAINING WALL SETOUT COORDINATES

POINTS	EASTING	NORTHING
P1	311770.234	899518.498
P2	311796.210	899514.270
P3	311772.021	899821.240
P4	311803.631	899518.923
P5	311848.254	899518.392
P6	311812.905	899513.320
P7	311882.733	899512.482
P8	311852.024	899506.318
P9	311829.314	899497.222
P10	311892.427	899481.880
P10A	311884.304	899485.581
P11	311886.464	899507.002
P12	311865.317	899532.228
P13	312000.109	899512.123
P14	311862.208	899504.945
P15	311810.311	899503.844
P16	311869.548	899543.077
P17	311711.481	899543.383
P18	311810.829	899571.443
P19	311854.481	899586.377
P20	311900.848	899586.060
P21	311873.962	899532.828
P22	311874.548	899528.841
P23	311864.074	899427.053
P24	311829.084	899423.207
P25	311921.134	899432.888
P26	311933.224	899432.489
P27	311885.285	899431.080
P28	311752.833	899448.810
P29	311750.895	899468.824
P30	311850.318	899505.325
P31	311841.204	899504.594
P32	311833.986	899502.622
P33	311834.336	899508.013
P34	311820.123	899518.017
P35	311810.311	899518.003
P36	311806.79	899502.062
P37	311800.891	899518.811
P38	311800.125	899545.724
P39	311811.28	899523.23
P40	311830.01	899508.05
P41	311813.58	899440.40
P42	311832.81	899438.85
P43	311848.45	899437.48
P44	311887.15	899438.85
P45	311848.59	899481.95



Handwritten signature
X 4/12/02

CONSENT ISSUE

SURVEYED BY:	DRAWN BY:	ADP
DATE SURVEYED:	DATE PLOTTED:	13.11.02
SDMAP REF:	CAD REFERENCE:	14152-05 SET/02
	CAD REF'S:	
DESIGNER:	ADP	APPROVED:
CHECKER:	AMB	JCT


THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LTD

HARRISON GRIERSON
HG
CONSULTING ENGINEERS SURVEYORS PLANNERS

PROJECT: **ST JUST ENTERPRISES LTD
COMPASS POINT SUBDIVISION
HALF MOON BAY**

TITLE: **ROAD CENTRE LINE LAYOUT AND
RETAINING WALL SETOUT PLAN**

PROJECT No:	DR14152.1
DRAWING No:	14152-05 A
A CONSENT ISSUE	REF/AMENDMENTS
ASPI (SCALE)	ORIGINAL SCALE: 1:750
REV (DATE)	REV (DATE)



**THIS PLAN FOR
INFORMATION
PURPOSES ONLY**

- NOTES:
1. ALL PROPOSED PAVEMENT WORKS ARE TO BE TO MCC STANDARDS.
 2. PROPOSED PAVEMENT ARE DESIGNED BASED ON A MAXIMUM SUBGRADE STRENGTH OF 0.8 U.S. SHOULD SUBGRADE STRENGTHS BE FOUND TO BE LOWER, THE CONTRACTOR MUST INFORM THE ENGINEER AND AN ALTERNATIVE PAVEMENT DESIGN WILL BE PROVIDED.
 3. THE "SITE WORKS" CONTRACT INVOLVES CONSTRUCTION OF FINAL GRADING LEVELS TO FINISH GRADING LEVELS. ALL UNDERDRAINED DRAINS WILL ALSO BE INSTALLED DURING PLACEMENT OF SUBGRADE AND ARE TO BE CONNECTED TO A SUITABLE CATCHPIT.
 4. THE CONTRACTOR IS RESPONSIBLE FOR LIAISON DIRECTLY WITH MCC AND OBTAINING THE NECESSARY CONSENTS/ APPROVALS FOR ANY WORKS WITHIN THE CHANNEL ROAD ROW.

[Signature]
4/12/02

SURVEYED BY:	DATE PLOTTED:	AMB
SCALE SHEET NO:	DATE:	08.02.02
SUBMAP REF:	CAD SYSTEMS/PLANNOV/3177-PAV2	
DESIGNED:	CAD SHEET'S: BASE-REF: CONT-REF:	
AMB 10/01	APPROVED:	AMC
CHECKED:	BY:	JTT


THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF AND MAY NOT BE REPRODUCED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LTD

HARRISON GRIERSON
HC
CONSULTING ENGINEERS SURVEYORS PLANNERS


PROJECT: CHILDREN'S HEALTH CAMP OF NEW ZEALAND PAKURANGA

TITLE: PROPOSED PAVEMENT PLAN 2


PROJECT No:	09.131.97.1
DRAWING No:	13177-PAV2
A DRAFT ISSUE	AMB/AMB ORIGINAL SCALE: 1:100
REVISIONS	BY DATE REVISION SCALE: 1:200




CROSS-SECTION A-A
SCALE 1:100 VER. 1:150 HOR



CROSS-SECTION B-B
SCALE 1:100 VER. 1:150 HOR



RETAINING WALL 3 LONGSECTION
SCALE 1:500 HORZ. 1:100 VER.



TYPICAL TIMBER POLE RETAINING WALL DETAIL
NOT TO SCALE

SURVEYED BY:	DRAWN BY:	ASD
DATE SURVEYED:	DATE PLOTTED:	18/11/02
SURMAP REF:	CAD REFERENCE:	14152-CROSS-SEC.ANG
DESIGNED:	APPROVED:	
CHECKED:		

HARRISON GRIERSON
HG
CONSULTING ENGINEERS SURVEYORS PLANNERS

PROJECT: ST JUST ENTERPRISES LIMITED
COMPASS POINT SUBDIVISION
HALF MOON BAY

TITLE: RETAINING WALL DETAILS AT BOUNDARY
OF HEALTH CAMP (WALL 3)

PROJECT No:	DR14152.1
DRAWING No:	14152-WALL
DRAWN SCALE:	AS SHOWN
BY DATE:	REMSZ SCALE:

X Benji
4/12/02

Appendix B

Critical Sections with Long Sections
from Civil Engineer Aireys

Marked on Latest civil set dated 10 April 2024



76 Compass Point Way

78 Compass Point Way

PROPOSED RETAINING WALL SEE ELEVATION DWG 203

80 Compass Point Way

EXTG TIMBER RETAINING WALL MAX HEIGHT 2.78m

82 Compass Point Way

84 Compass Point Way

SITE PLAN 1:500

COMPASS POINT WAY

PROPOSED RETAINING WALL SEE ELEVATION DWG 204

ARA-TAI

Isopachs shown have been calculated from existing ground level to FFL

ELEVATIONS TABLE			
NUMBER	MIN. ELEVATION	MAX. ELEVATION	COLOUR
1	-3.00	-2.00	Red
2	-2.00	-1.00	Orange
3	-1.00	0.00	Light Orange
4	0.00	1.00	Light Green
5	1.00	2.00	Green
6	2.00	3.00	Dark Green
7	3.00	4.00	Very Dark Green

STRUCTURAL ROOT ZONE TBC

BLOCK C

PIGEON MOUNTAIN ROAD

1 DP 212125 1.4073 ha

EARTHWORKS AREA (within site): 14000m² (NOTE: AREA BEHIND EXTG WEST BDY RETAINING WALL WILL NOT BE DISTURBED = 80m²)

EARTHWORKS VOLUMES (Total): Cut = 4076m³ Fill = 6690m³ Net Fill = 2614m³

EARTHWORKS VOLUMES (Ara Tai Reserve): AREA=225m² Cut = 19m³ Fill = 8m³ Net Cut = 11m³

EARTHWORKS VOLUMES (Pigeon Mt berm): AREA=245m² Cut = 35m³ Fill = 0m³ Net Cut = 35m³

Volumes are from existing ground level to FFL (including topsoil, subgrade, concrete).

Note: Earthworks volumes for consent only. Not to be used for tender purposes.



CIVIL, STRUCTURAL AND FIRE ENGINEERS

AIREY CONSULTANTS LTD TEL: (09) 534 6523 www.aireys.co.nz

TAKAPUNA BOTANY QUEENSTOWN

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD HALF MOON BAY

NOTES:

REV	AMENDMENT	DATE	BY
6	WEST BDY RET WALL REVISED	10/04/2024	LP
5	RET WALL SYMBOLS TO MATCH ARCH	09/04/2024	LP
4	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
3	SECTION 3 RELOCATED	08/02/2024	JC
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - LAYOUT/LEVELS REVISED	20/10/2023	LP

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN: SW

DRAWN: LP

CHECKED: RT


DATE: 22/05/23

SCALE: 1:500 @ A3

DO NOT SCALE FROM DRAWINGS

© Copyright 2021 Airey Consultants Ltd

ORIGINAL SIZE:



DRAWING TITLE:

SITE PLAN EARTHWORKS

JOB No:

220571-1

SHEET No:

200

REV:

6


PROPOSED RETAINING WALL SEE ELEVATION DWG 204

SEE EAST BDY ELEVATION DWG 204

RETAINING WALLS: FOR TYPE AND HEIGHT OF PROPOSED WALLS REFER ARCHITECTS PLAN RA0104

SEE SOUTH BDY ELEVATION DWG 204a

A:\220571-1\3 Pigeon Mountain Rd\CAO\WORKING DRAWINGS\3 PIGEON MOUNTAIN RD 220571-1 EW_November 23_recover.dwg, 10/04/2024 3:47:32 pm, DWG To PDF.pc3



76 Compass Point Way

78 Compass Point Way

80 Compass Point Way

82 Compass Point Way

84 Compass Point Way

COMPASS POINT WAY

ARA-TAI

PIGEON MOUNTAIN ROAD



CIVIL, STRUCTURAL AND FIRE ENGINEERS

AIREY CONSULTANTS LTD
TEL: (09) 534 6523 www.aireys.co.nz

TAKAPUNA BOTANY QUEENSTOWN

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD
HALF MOON BAY

1
DP 212125
1.4073 ha

NOTES:

6	WEST BDY RET WALL REVISED	10/04/2024	LP
5	LOT 2 BDY REVISED	09/04/2024	LP
4	LOT 15 & 16 FPATH ADDED	30/03/2024	LP
3	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - LAYOUT LEVELS REVISED	20/10/2023	LP
REV	AMENDMENT	DATE	BY

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN: SW

DRAWN: LP

CHECKED: RT


DATE: 22/05/23

SCALE: 1:500 @ A3

DO NOT SCALE FROM DRAWINGS

© Copyright 2021 Airey Consultants Ltd

ORIGINAL SIZE:



DRAWING TITLE:

SITE PLAN
PROPOSED LEVELS

JOB No:

220571-1

SHEET No:

202

REV:

6

SITE PLAN
1:500



A:\220571-1\220571_3 Pigeon Mountain Rd\CAD\WORKING DRAWINGS\3 PIGEON MOUNTAIN RD 220571-1_EW_November 23_recover.dwg, 10/04/2024, 3:46:52 pm, DWG To PDF.pc3



AIREY CONSULTANTS LTD
 TEL: (09) 534 6523 www.aireys.co.nz
 TAKAPUNA BOTANY QUEENSTOWN

CLIENT:
 HND HMB LTD

JOB TITLE:
 3 PIGEON MOUNTAIN ROAD
 HALF MOON BAY


NOTES:

4	LOT 40 REVISION	09/04/2024	LP
3	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - RETAINING WALL REVISION	20/10/2023	LP
REV	AMENDMENT	DATE	BY

DRAWING STATUS:
FINAL



ISSUE PURPOSE:
RESOURCE CONSENT

DESIGN:	SW
DRAWN:	LP
CHECKED:	RT
DATE:	22/05/2023
SCALE:	1:250 @ A3
DO NOT SCALE FROM DRAWINGS	
© Copyright 2021 Airey Consultants Ltd	



DRAWING TITLE:
 RETAINING WALL ELEVATIONS

JOB No:	SHEET No:	REV:
220571-1	203	4



WEST BDY RETAINING WALL 2 ELEVATION
 VERT 1:100
 HORIZ 1:250

J:\220000\220571_3 Pigeon Mountain Rd\CAD\WORKING DRAWINGS\3 PIGEON MOUNTAIN RD 220571-1 Drainage.dwg, 9/04/2024 12:56:29 pm, DWG To PDF.plt3

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD
HALF MOON BAY

NOTES:

REV	AMENDMENT	DATE	BY
3	S92 REVISIONS - 87 DWELLINGS	26/03/2024	LP
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - RETAINING WALL REVISION	20/10/2023	LP

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN: SW

DRAWN: LP

CHECKED: RT


DATE: 22/05/2023

SCALE: 1:100 @ A3

DO NOT SCALE FROM DRAWINGS

© Copyright 2021 Airey Consultants Ltd

ORIGINAL SIZE:



DRAWING TITLE:

CROSS-SECTIONS THROUGH
WEST BDY RETAINING WALL

JOB No:


220571-1

SHEET No:


206

REV:

3



SECTION 1



SECTION 2

CLIENT:

HND HMB LTD

JOB TITLE:

3 PIGEON MOUNTAIN ROAD
HALF MOON BAY

NOTES:

REV	AMENDMENT	DATE	BY
3	SECTION 3 RELOCATED	08/02/2024	JC
2	S92 REVISIONS - 88 LOTS	05/02/2024	LP
1	S92 - RETAINING WALL REVISION	20/10/2023	LP

DRAWING STATUS:

FINAL

ISSUE PURPOSE:

RESOURCE CONSENT

DESIGN: SW

DRAWN: LP

CHECKED: RT


DATE: 22/05/2023

SCALE: 1:100 @ A3

DO NOT SCALE FROM DRAWINGS

© Copyright 2021 Airey Consultants Ltd

ORIGINAL SIZE:



DRAWING TITLE:

CROSS-SECTIONS THROUGH
WEST BDY RETAINING WALL

JOB No:


220571-1

SHEET No:


206a

REV:

3



SECTION 3



SECTION 4

Appendix C

Analysis Outputs and Design Calcs

- Retaining wall information summary updated
on 05 Feb 2024

Western Retaining Wall Information Summary

Western Boundary Existing Retaining Wall Information updated 2024.04.10												
Existing Timber Retaining Wall Top Level (From North to South)	Existing Toe Level	Design Finished Floor Levels	550 mm Sub Excavation Levels	Proposed Excavation Depth (m)	Approximate Groundwater Drawdown Depth (m) (1.4 m bgl interpreted)	Existing Retaining Height (m)	Proposed Design RH (m)	Representative Design RH Range (m)	Covering Lot No #	Deepest Excavation Spot	Nearest corresponding piezo. No	Analysed Section
/	/	/	/	/	/	No EXTG. Retaining Wall	/	/	Lot #1	Fill-up areas without retaining wall		
12.48	11.22	9.71	9.16	2.1	0.7	1.26	3.32	3.0 - 4.5	Lot # 88	Lot 88 Southwestern Corner	HA09	
13.56	12.78	10.70	10.15	2.6	1.2	0.78	3.41					
14.48	13.51	10.70	10.15	3.4	2.0	0.97	4.33					Section 1
16.13	15.09	12.20	11.65	3.4	2.0	1.04	4.48	3.5 - 4.5	Lot # 83 - 86	Lot 85 Southwestern Corner		Section 2
16.29	15.28	13.20	12.65	2.6	1.2	1.01	3.64					
16.84	15.79	13.20	12.65	3.1	1.7	1.05	4.19					
18.40	16.77	14.70	14.15	2.6	1.2	1.64	4.25					
18.62	17.67	14.70	14.15	3.5	2.1	0.95	4.47	4.0 - 4.5	Lot # 79 - 82	Lot 79 Southwestern Corner	HA10	
19.05	18.01	15.10	14.55	3.5	2.1	1.04	4.50					Section 3
18.77	17.74	15.10	14.55	3.2	1.8	1.03	4.22					
19.27	17.87	16.60	16.05	1.8	0.4	1.40	3.22	3.0 - 3.5	Lot # 41- 42			
19.48	18.71	17.00	16.45	2.3	0.9	0.77	3.03					
19.70	17.98	17.00	16.45	1.5	0.1	1.73	3.25					Section 4 (will adopt Section 1 design)

Plaxis Material Properties

Input

Project; 3 Pigeon Mountain Road

Number; J00538

Job; Western Boundary Retaining Wall

Analysed Sections			Section 1 - Existing Wall	Section 2 - Existing Wall	Section 3 - Existing Wall	Section 4 - Existing Wall
	Existing Retaining Height		1.0 m	2.0 m	2.8 m	1.5 m
Input Wall Properties	Timber Pole Category		Normal	Normal	Normal	Normal
	Unit Weight of Timber Pole	γ_p	5.3955	5.3955	5.3955	5.3955
	Unit Weight of Soil	γ_s	17	17	17	17
	Diameter of Pile	d	0.2	0.25	0.35	0.2
	Radius	r	0.1	0.125	0.175	0.1
	Pile Spacing	s	1.2	1.1	1.0	1.2
Output Wall Properties	Area	A	0.0261799	0.0446249	0.0962113	0.0261799
	Modulus of Elasticity	E	8.7	8.7	8.7	8.7
			8.70E+06	8.70E+06	8.70E+06	8.70E+06
	Second Moment of Area	I	6.545E-05	0.0001743	0.0007366	6.545E-05
	Plaxis Virtual Depth	d	0.1731	0.2168	0.3031	0.2598
	Plaxis Virtual Width of Pile	b_p	0.1512417	0.2058344	0.3174242	0.1007696
	Virtual width of soil between piles	b_s	0.8487583	0.7941656	0.6825758	0.8992304
Weighted average unit weight of wall	γ_w	15.244916	14.611395	13.316451	15.830619	
Plaxis Input Parameters	Axial Stiffness	EA	2.28E+05	3.88E+05	8.37E+05	2.28E+05
	Flexural Stiffness	EI	5.69E+02	1.52E+03	6.41E+03	5.69E+02
	Weight of Wall	w	0	0	0	0

Adopted Analysis Soil Parameters

Layer Numbering System	Strata Name	Material Analysis Model	Unit Weight, γ (kN/m ³)	Effective Cohesion, c' (kPa)	Effective Friction Angle, ϕ' (°)	Undrained Shear Strength, s_u (kPa)	Effective Young's Modulus, E' (MPa)	Permeability $k_v = kh$ (m/s)
①	Fill	Mohr-Coloumb	17	7	32	70	10	1.0E-07
②	Puketoka Formaiton	Mohr-Coloumb	17	3	30	50	7	1.0E-07
③	CW - HW ECBF	Mohr-Coloumb	17	7	32	100	15	1.0E-07
④	MW - SW ECBF	Mohr-Coloumb	18	20	38	400	50	1.0E-08

UC wall Plaxis 2D properties

Plaxis Material Properties					
Date:	8/02/2024		Input		
Project:	3 Pigeon Mountain Road				
Number:	J00538				
Job:	Western Boundary Retaining Wall				
Information	Analysed Section		Section 1	Section2	Section3
Input Wall Properties	Steel Pile Designation		250UC89.5	250UC89.5	250UC89.5
	Unit Weight of Steel	γ_{st}	77	77	77
	Unit Weight of Soil	γ_s	17	17	17
	Pile Spacing	s	1.0	1.0	1.0
Output Wall Properties	Area	A	11400	11400	11400
			0.0114	0.0114	0.0114
			0.0114	0.0114	0.0114
	Modulus of Elasticity	E	200	200	200
			2.00E+08	2.00E+08	2.00E+08
	Second Moment of Area	I	143,000,000	143,000,000	143,000,000
			0.000143	0.000143	0.000143
			0.000143	0.000143	0.000143
	Plaxis Virtual Depth	d	0.388	0.388	0.388
Plaxis Virtual Width of Pile	b_p	0.02938	0.02938	0.02938	
Virtual width of soil between piles	b_s	0.97062	0.97062	0.97062	
Weighted average unit weight of wall	γ_w	18.76	18.76	18.76	
Plaxis Input Parameters	Axial Stiffness	EA	2.28E+06	2.28E+06	2.28E+06
	Flexural Stiffness	EI	2.86E+04	2.86E+04	2.86E+04
	Weight of Wall	w	0.214	0.214	0.214
Design Strength of Piles					
ULS Design Actions	Plaxis Pile Moment	M	60.0	60.0	60.0
	Plaxis Pile Shear	V	60.0	60.0	60.0
	Pile Spacing	s	1.0	1.0	1.0
	Earth Load Factor		1.5	1.5	1.5
	Design Moment	M*	90.0	90.0	90.0
	Design Shear	V*	90.0	90.0	90.0
Section Properties	Strength Reduction Factor for Bending and Shear	ϕ	0.9	0.9	0.9
	Yield Strength	f_y	500	500	500
	Second Moment of Area at Critical Depth	Z	1,100,000	1,100,000	1,100,000
	Web Shear Area	A_w	2362.5	2362.5	2362.5
Section Capacity Checks	Design Bending Moment	M*	90.0	90.0	90.0
	Design Bending Strength	ϕM	495.0	495.0	495.0
	Pile ok for Bending	M*/ϕM	18%	18%	18%
	Design Shear Force	V*	90.0	90.0	90.0
	Design Shear Strength	ϕV	637.9	637.9	637.9
	Pile ok for Shear	V*/ϕV	14%	14%	14%

Section 1

Design Spreadsheets Calculations and Plaxis Analysis Outputs

Section 1 Plaxis Analysis Phases

Phase 0: Initial Phase (Initialize the model)

Phase 1: School Development and Western Timber Retaining Wall Installation (Assumed 1V: 1H cantilever to embedment ratio)

Phase 2: Neighboring Property Construction (Imposing Line loads)

Phase 3: Install Proposed Retaining Wall (Previous phase displacement reset)


Phase 4: Backfilling the gaps between two walls

Phase 5: Excavation to target level (550 mm below FGL)
(Steady state groundwater drawdown analysis)

Phase 5.1: Worst Ground Water Scenario


Phase 5.2: Seismic Scenario

Section 1 Ground Profile




Section 1 Analysis Ground Settlement Contours

Phase 5 Settlement Contours




Phase 5 Settlements at different interval points for calculating differential settlement




Phase 5 differential Settlements at different interval points calculation details

Section 1	Coordinates		Settlement	Pair	x difference	uy difference	Settlement change rate (m/m)
	x (m)	y (m)	u_y (mm)				
				B to 1	-1.83	0.085	-21529.41176
B	-18.71	14.48	-3.378	B to 2	-3.75	0.666	-5630.630631
1	-16.88	14.48	-3.463	B to 3	-5.76	1.449	-3975.15528
2	-14.96	14.48	-4.044	B to 4	-7.88	2.172	-3627.992634
3	-12.95	14.48	-4.827	B to 5	-10.13	2.702	-3749.074759
4	-10.83	14.48	-5.55	B to 6	-12.51	2.762	-4529.326575
5	-8.58	14.48	-6.08	B to A	-15.01	2.122	-7073.515551
6	-6.2	14.48	-6.14	1 to 2	-1.92	0.581	-3304.64716
A	-3.7	14.48	-5.5	1 to 3	-3.93	1.364	-2881.231672
				1 to 4	-6.05	2.087	-2898.89794
				1 to 5	-8.3	2.617	-3171.570501
				1 to 6	-10.68	2.677	-3989.54053
				1 to A	-13.18	2.037	-6470.29946
				2 to 3	-2.01	0.783	-2567.049808
				2 to 4	-4.13	1.506	-2742.363878
				2 to 5	-6.38	2.036	-3133.595285
				2 to 6	-8.76	2.096	-4179.389313
				2 to A	-11.26	1.456	-7733.516484
				3 to 4	-2.12	0.723	-2932.226833
				3 to 5	-4.37	1.253	-3487.629689
				3 to 6	-6.75	1.313	-5140.898705
				3 to A	-9.25	0.673	-13744.42793
				4 to 5	-2.25	0.53	-4245.283019
				4 to 6	-4.63	0.59	-7847.457627
				4 to A	-7.13	-0.05	142600
				5 to 6	-2.38	0.06	-39666.66667
				5 to A	-4.88	-0.58	8413.793103
				6 to A	-2.5	-0.64	3906.25
						Max Ratio	2567.049808


Phase 5.1 Settlement Contours



Predicted settlement
at Existing WW Line
Coordinates (-3.47,
12.68)




Predicted settlement at Existing SW Line coordinates(-2.0, 11.7)




Section 1 Analysis Lateral Deflection

Phase 5 Wall Lateral Deflection Profile



Total displacements u_x (scaled up 500 times)
Maximum value = $3.311 \cdot 10^{-3}$ m (Element 3 at Node 30)
Minimum value = $0.3486 \cdot 10^{-3}$ m (Element 12 at Node 1815)

Phase 5.1 Wall Lateral Deflection Profile




Total displacements u_x (scaled up 200 times)

Maximum value = 0.01339 m (Element 3 at Node 30)

Minimum value = 2.566×10^{-3} m (Element 22 at Node 4874)

Section 1 Analysis Wall Internal Forces Diagram

Phase 5 Wall Bending Moment Diagram




Bending moments M (scaled up 0.0500 times)

Maximum value = 10.88 kN m/m (Element 18 at Node 3449)


Minimum value = -18.46 kN m/m (Element 12 at Node 1815)

Phase 5 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)
Maximum value = 11.04 kN/m (Element 14 at Node 2417)
Minimum value = -16.28 kN/m (Element 12 at Node 1812)

Phase 5 Wall Axial Force Diagram



Axial forces N (scaled up 0.0500 times)
Maximum value = 8.430 kN/m (Element 20 at Node 4178)
Minimum value = -27.12 kN/m (Element 12 at Node 1812)

Phase 5.1 Wall Bending Moment Diagram



Bending moments M (scaled up 0.0500 times)

Maximum value = 10.50 kN m/m (Element 18 at Node 3449)

Minimum value = -19.61 kN m/m (Element 12 at Node 1912)

Phase 5.1 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)

Maximum value = 12.52 kN/m (Element 15 at Node 2536)

Minimum value = -19.42 kN/m (Element 11 at Node 1812)

Phase 5.1 Wall Axial Force Diagram




Axial forces N (scaled up 0.0500 times)

Maximum value = 16.57 kN/m (Element 19 at Node 4176)

Minimum value = -19.37 kN/m (Element 11 at Node 1812)

Phase 5.2 Wall Bending Moment Diagram




Bending moments M (scaled up 0.0500 times)

Maximum value = 33.75 kN/m (Element 17 at Node 3091)


Minimum value = -26.86 kN/m (Element 12 at Node 1814)

Phase 5.2 Wall Shear Force Diagram



Shear forces Q (scaled up 0.0500 times)
Maximum value = 24.89 kN/m (Element 14 at Node 2416)
Minimum value = -24.81 kN/m (Element 11 at Node 1812)

Phase 5.2 Wall Axial Force Diagram




Axial forces N (scaled up 0.0500 times)

Maximum value = 1.119 kN/m (Element 21 at Node 4588)


Minimum value = -38.86 kN/m (Element 11 at Node 1812)

Section 1 Factor of Safety Analysis

Integrated FoS chart




Groundwater flow map



Groundwater flow |q| (scaled up 100 times)

Maximum value = 0.01036 m/day (Element 470 at Stress point 5638)
Minimum value = $1.122 \cdot 10^{-9}$ m/day (Element 209 at Stress point 2499)

Groundwater discharge rate over excavation length



Section 2

Design Spreadsheets Calculations and Plaxis Analysis Outputs

Section 2 Plaxis Analysis Phases

Phase 0: Initial Phase (Initialize the model)

Phase 1: School Development and Western Timber Retaining Wall Installation (Assumed 1: 1 cantilever to embedment ratio)

Phase 2: Neighboring Property Construction (Imposing Line loads)

Phase 3: Install Proposed Retaining Wall (Previous phase displacement reset)

Phase 4: Backfilling the gaps between two walls

Phase 5: Excavation to target level (550 mm below FGL)
(Steady state groundwater drawdown analysis)

Phase 5.1: Worst Ground Water Scenario


Phase 5.2: Seismic Scenario

Section 2 Ground Profile

10 m wide x10 kPa foundation
Surcharge


Proposed Wall

Wall Top RL 16.13 m




Section 2 Analysis Ground Settlement Contours

Phase 5 Settlement Contours




Phase 5 Settlements at different interval points for calculating differential settlement



Phase 5 differential Settlements at different interval points calculation details

Section 2	Coordinates		Settlement				Pair	x difference	uy difference	Settlement change rate (m/m)
	x (m)	y (m)	u _y (mm)							
							B to 1	-2.84	0.3304	-8595.641646
B	-23	16.13	-0.7416	(-23,16.13)			B to 2	-5.71	0.6424	-8888.542964
1	-20.16	16.13	-1.072	(-20.16,16.13)			B to 3	-8.6	0.9784	-8789.860998
2	-17.29	16.13	-1.384	(-17.29,16.13)			B to 4	-11.4	1.3384	-8517.632995
3	-14.4	16.13	-1.72	(-14.4,16.13)			B to 5	-14.3	1.7414	-8211.783622
4	-11.6	16.13	-2.08	(-11.6,16.13)			B to 6	-17.11	2.1484	-7964.066282
5	-8.7	16.13	-2.483	(-8.7,16.13)			B to A	-20	2.6284	-7609.191904
6	-5.89	16.13	-2.89	(-5.89,16.13)			1 to 2	-2.87	0.312	-9198.717949
A	-3	16.13	-3.37	(-3,16.13)			1 to 3	-5.76	0.648	-8888.888889
							1 to 4	-8.56	1.008	-8492.063492
							1 to 5	-11.46	1.411	-8121.899362
							1 to 6	-14.27	1.818	-7849.284928
							1 to A	-17.16	2.298	-7467.362924
							2 to 3	-2.89	0.336	-8601.190476
							2 to 4	-5.69	0.696	-8175.287356
							2 to 5	-8.59	1.099	-7816.196542
							2 to 6	-11.4	1.506	-7569.721116
							2 to A	-14.29	1.986	-7195.367573
							3 to 4	-2.8	0.36	-7777.777778
							3 to 5	-5.7	0.763	-7470.51114
							3 to 6	-8.51	1.17	-7273.504274
							3 to A	-11.4	1.65	-6909.090909
							4 to 5	-2.9	0.403	-7196.029777
							4 to 6	-5.71	0.81	-7049.382716
							4 to A	-8.6	1.29	-6666.666667
							5 to 6	-2.81	0.407	-6904.176904
							5 to A	-5.7	0.887	-6426.155581
							6 to A	-2.89	0.48	-6020.833333
									Max Ratio	6020.833333

Phase 5.1 Settlement Contours



Total displacements u_y (scaled up 50.0 times)

Maximum value = 9.809×10^{-3} m (Element 480 at Node 2541)


Minimum value = -6.983×10^{-3} m (Element 455 at Node 3808)

Total displacements u_y (scaled up 50.0 times)

Maximum value = 9.809×10^{-3} m (Element 480 at Node 2541)


Minimum value = -6.983×10^{-3} m (Element 455 at Node 3808)

Predicted settlement at Existing WW Line coordinates (-3.7, 14.12)



Hint box

Soil data		
Soil element number	143	
X	-3.708	m
Y	14.11	m
Current value		
u_y	$-3.229 \cdot 10^{-3}$	m




Total displacements u_y (scaled up 50.0 times)
 Maximum value = 0.01056 m (Element 467 at Node 5094)
 Minimum value = $-6.033 \cdot 10^{-3}$ m (Element 151 at Node 1351)

```


Session Model history
commands can be called as follows:
command [target] [param1 [param2 [...]]]
for example:
getresults Phases[-1] ResultTypes.soil.Utot "node"
info Utot_Phase_1_Soil_1
Use the "info" command to access information about an object
Use the "commands" command to view the command parameters expected by the commands of the target object
  
```

Predicted settlement at Existing SW Line coordinates (-2.1. 13.17)



Hint box

Soil data			
Soil element number	414		
X	-2.085	m	
Y	13.11	m	
Current value			
u_y	$-3.096 \cdot 10^{-3}$	m	




Total displacements u_y (scaled up 50.0 times)
 Maximum value = 0.01056 m (Element 467 at Node 5094)
 Minimum value = $-6.033 \cdot 10^{-3}$ m (Element 151 at Node 1351)

```


Session Model history
Commands can be called as follows:
command [target] [param1 [param2 [...]]]
for example:
getresults Phases[-1] ResultTypes.Soil.Utot "node"
info Utot_Phase_1_Soil_1
Use the "info" command to access information about an object
Use the "commands" command to view the command parameters expected by the commands of the target object
  
```

Section 2 Analysis Lateral Deflection

Phase 5 Wall Lateral Deflection Profile




Phase 5.1 Wall Lateral Deflection Profile



Total displacements u_x (scaled up 200 times)
Maximum value = 0.01960 m (Element 3 at Node 1810)
Minimum value = $1.451 \cdot 10^{-3}$ m (Element 20 at Node 2654)

Section 2 Analysis Wall Internal Forces Diagram

Phase 5 Wall Bending Moment Diagram




Bending moments M (scaled up 0.100 times)

Maximum value = 1.315 kN m/m (Element 18 at Node 2338)


Minimum value = -27.28 kN m/m (Element 11 at Node 2055)

Phase 5 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)
Maximum value = 10.12 kN/m (Element 14 at Node 2255)
Minimum value = -19.61 kN/m (Element 9 at Node 2107)

Phase 5 Wall Axial Force Diagram




Axial forces N (scaled up 0.100 times)
Maximum value = 8.925 kN/m (Element 18 at Node 2337)
Minimum value = -19.68 kN/m (Element 9 at Node 2107)

Phase 5.1 Wall Bending Moment Diagram



Phase 5.1 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)

Maximum value = 10.96 kN/m (Element 14 at Node 2255)

Minimum value = -19.48 kN/m (Element 9 at Node 2107)


Minimum value = -19.48 kN/m (Element 9 at Node 2107)

Phase 5.1 Wall Axial Force Diagram



Axial forces N (scaled up 0.100 times)
Maximum value = 7.204 kN/m (Element 18 at Node 2337)
Minimum value = -19.74 kN/m (Element 9 at Node 2107)

Phase 5.2 Wall Bending Moment Diagram




Bending moments M (scaled up 0.0500 times)

Maximum value = 3.330 kN m/m (Element 18 at Node 2338)


Minimum value = -56.30 kN m/m (Element 11 at Node 2055)

Phase 5.2 Wall Shear Force Diagram



Shear forces Q (scaled up 0.0500 times)
Maximum value = 23.40 kN/m (Element 14 at Node 2255)
Minimum value = -37.73 kN/m (Element 9 at Node 2107)

Phase 5.2 Wall Axial Force Diagram



Axial forces II (scaled up 0.0500 times)

Maximum value = 12.43 kN/m (Element 17 at Node 2305)

Minimum value = -32.39 kN/m (Element 9 at Node 2107)

Section 2 Factor of Safety Analysis





Chart 1
Node 1645 (NG) *
Node 1652 (WG) *
Node 1810 (Seismic) *

Groundwater flow map




Groundwater flow |q| (scaled up 500 times)

Maximum value = $1.482 \cdot 10^{-3}$ m/day (Element 425 at Stress point 5089)

Minimum value = $2.888 \cdot 10^{-12}$ m/day (Element 159 at Stress point 1897)

Groundwater discharge rate over excavation length



Groundwater flow |q| (scaled up 1.00*10⁻³ times)

Maximum value = 1.313*10⁻³ m/day

Minimum value = 0.01247*10⁻³ m/day

Total discharge is 1.347*10⁻³ m³/day/m

Section 3

Design Spreadsheets Calculations and Plaxis Analysis Outputs

Section 3 Plaxis Analysis Phases

Phase 0: Initial Phase (Initialize the model)

Phase 1: School Development and Western Timber Retaining Wall
Installation (Assumed 1V: 1H cantilever to embedment ratio)

Phase 2: Neighboring Property Construction (Imposing Line loads)

Phase 3: Install Proposed Retaining Wall (Previous phase displacement
reset)

Phase 4: Backfilling the gaps between two walls

Phase 5: Excavation to target level (550 mm below FGL)

(Steady state groundwater drawdown analysis)

Phase 5.1: Worst Ground Water Scenario

Phase 5.2: Seismic Scenario

Section 3 Ground Profile

10 m wide x10 kPa foundation
Surcharge

Proposed Wall

Point B

Point A

Wall Top RL 19.05 m

Existing RL 17.36

Target R.L. 14.55

EXTG FILL


Puketoka Formation

CW-HW ECBF

MW-SW ECBF


Point C (WW line)

Point D(SW line)




Section 3 Analysis Ground Settlement Contours

Phase 5 Settlement Contours




Phase 5 Settlements at different interval points for calculating differential settlement



Phase 5 differential Settlements at different interval points calculation details


Section 3	Coordinates		Settlement	Pair	x difference	uy difference	Settlement change rate (m/m)
	x (m)	y (m)	u_y (mm)				
				B to 1	-2.76	0.518	-5328.185328
B	-19	19.05	-1.481	B to 2	-5.45	1.133	-4810.238305
1	-16.24	19.05	-1.999	B to 3	-8.2	1.859	-4410.973642
2	-13.55	19.05	-2.614	B to 4	-10.931	2.551	-4284.98628
3	-10.8	19.05	-3.34	B to 5	-12.282	2.872	-4276.462396
4	-8.069	19.05	-4.032	B to 6	-13.633	3.215	-4240.435459
5	-6.718	19.05	-4.353	B to A	-15	3.663	-4095.004095
6	-5.367	19.05	-4.696	1 to 2	-2.69	0.615	-4373.98374
A	-4	19.05	-5.144	1 to 3	-5.44	1.341	-4056.674124
				1 to 4	-8.171	2.033	-4019.183473
				1 to 5	-9.522	2.354	-4045.029737
				1 to 6	-10.873	2.697	-4031.5165
				1 to A	-12.24	3.145	-3891.891892
				2 to 3	-2.75	0.726	-3787.878788
				2 to 4	-5.481	1.418	-3865.303244
				2 to 5	-6.832	1.739	-3928.694652
				2 to 6	-8.183	2.082	-3930.355427
				2 to A	-9.55	2.53	-3774.703557
				3 to 4	-2.731	0.692	-3946.531792
				3 to 5	-4.082	1.013	-4029.615005
				3 to 6	-5.433	1.356	-4006.637168
				3 to A	-6.8	1.804	-3769.40133
				4 to 5	-1.351	0.321	-4208.722741
				4 to 6	-2.702	0.664	-4069.277108
				4 to A	-4.069	1.112	-3659.172662
				5 to 6	-1.351	0.343	-3938.77551
				5 to A	-2.718	0.791	-3436.156764
				6 to A	-1.367	0.448	-3051.339286
						Max Ratio	3051.339286

Phase 5.1 Settlement Contours




Total displacements u_y (scaled up 50.0 times)
Maximum value = 0.01706 m (Element 415 at Node 1047)
Minimum value = $-8.284 \cdot 10^{-3}$ m (Element 165 at Node 2518)

Predicted settlement at Existing
WW Line
Coordinates (-3.64, 17.36)



Hint box


Soil data		
Soil element number	151	
X	-3.641	m
Y	17.36	m
Current value		
u_y	$-5.153 \cdot 10^{-3}$	m



Total displacements u_y (scaled up 50.0 times)
 Maximum value = 0.01547 m (Element 415 at Node 1047)
 Minimum value = $-9.570 \cdot 10^{-3}$ m (Element 161 at Node 2547)


Commands can be called as follows:
 command [target] [param1 [param2 [...]]]
 for example:
 getresults Phases[-1] ResultTypes.Soil.Utot "node"
 info Utot_Phase_1_Soil_1
 Use the "info" command to access information about an object
 Use the "commands" command to view the command parameters expected by the commands of the target object

Predicted settlement at Existing SW Line coordinates(-2.13, 17.0)



Hint box

Soil data		
Soil element number	159	
X	-2.149	m
Y	16.97	m
Current value		
u_y	$-5.808 \cdot 10^{-3}$	m




Total displacements u_y (scaled up 50.0 times)
 Maximum value = 0.01547 m (Element 415 at Node 1047)
 Minimum value = $-9.570 \cdot 10^{-3}$ m (Element 161 at Node 2547)

```

Commands can be called as follows:
command [target] [param1 [param2 [...]]]
for example:
getresults Phases[-1] ResultTypes.Soil.Utot "node"
info Utot_Phase_1_Soil_1
Use the "info" command to access information about an object
Use the "commands" command to view the command parameters expected by the commands of the target object
  
```


Section 3 Analysis Lateral Deflection

Phase 5 Wall Lateral Deflection Profile



Total displacements u_x (scaled up 200 times)
Maximum value = 0.01669 m (Element 4 at Node 91)
Minimum value = $-0.7063 \cdot 10^{-3}$ m (Element 23 at Node 3279)


Phase 5.1 Wall Lateral Deflection Profile




Total displacements u_x (scaled up 100 times)
Maximum value = 0.02010 m (Element 4 at Node 91)
Minimum value = -0.2870*10⁻³ m (Element 24 at Node 3293)

Section 3 Analysis Wall Internal Forces Diagram

Phase 5 Wall Bending Moment Diagram



Phase 5 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)

Maximum value = 10.87 kN/m (Element 19 at Node 2360)

Minimum value = -17.49 kN/m (Element 14 at Node 1058)

Phase 5 Wall Axial Force Diagram




Axial forces N (scaled up 0.100 times)

Maximum value = 1.672 kN/m (Element 26 at Node 4094)

Minimum value = -19.76 kN/m (Element 14 at Node 1058)

Phase 5.1 Wall Bending Moment Diagram




Bending moments M (scaled up 0.0500 times)

Maximum value = 5.347×10^{-3} kN m/m (Element 4 at Node 93)

Minimum value = -30.15 kN m/m (Element 17 at Node 1892)

Phase 5.1 Wall Shear Force Diagram




Shear forces Q (scaled up 0.0500 times)

Maximum value = 11.71 kN/m (Element 19 at Node 2359)


Minimum value = -18.20 kN/m (Element 14 at Node 1058)

Phase 5.1 Wall Axial Force Diagram



Axial forces N (scaled up 0.100 times)
Maximum value = 4.541 kN/m (Element 25 at Node 4092)
Minimum value = -18.71 kN/m (Element 14 at Node 1058)

Phase 5.2 Wall Bending Moment Diagram




Bending moments M (scaled up 0.0500 times)

Maximum value = 2.637×10^{-3} kN m/m (Element 4 at Node 93)


Minimum value = -51.98 kN m/m (Element 17 at Node 1889)

Phase 5.2 Wall Shear Force Diagram



Shear forces Q (scaled up 0.0500 times)
Maximum value = 20.59 kN/m (Element 19 at Node 2360)
Minimum value = -33.55 kN/m (Element 14 at Node 1058)

Phase 5.2 Wall Axial Force Diagram




Axial forces N (scaled up 0.0500 times)


Maximum value = -0.07279 kN/m (Element 4 at Node 91)

Minimum value = -34.98 kN/m (Element 14 at Node 1058)

Section 3 Factor of Safety Analysis



Groundwater flow map



Groundwater flow $|q|$ (scaled up 500 times)

Maximum value = $4.146 \cdot 10^{-3}$ m/day (Element 378 at Stress point 4525)

Minimum value = $4.503 \cdot 10^{-12}$ m/day (Element 103 at Stress point 1227)

Groundwater discharge rate over excavation length



Groundwater flow |q| (scaled up 500 times)


Maximum value = $2.359 \cdot 10^{-3}$ m/day

Minimum value = $0.03806 \cdot 10^{-3}$ m/day

Total discharge is $1.686 \cdot 10^{-3}$ m³/day/m

Appendix D

Preliminary Retaining Wall Design Drawings



LOCALITY PLAN
N.T.S

3 PIGEON MOUNTAIN ROAD HALF MOON BAY AUCKLAND WESTERN BOUNDARY RETAINING WALLS

DRAWING SCHEDULE

DRAWING NUMBER	DRAWING NAME	SCALE (A3)	ISSUES
001	TITLE SHEET AND DRAWING SCHEDULE	-	3
010	SITE PLAN	1:600	3
100	PILE TYPE DIAGRAM	1:250	3
101	FACE ELEVATION 01	1:250	3
102	FACE ELEVATION 02	1:250	3
201	TYPICAL SECTION DETAILS SECTION 3	1:50	3
300	MONITORING PLAN	1:600	3



27C WAIPAREIRA AVENUE
HENDERSON
PH: 027 557 7234
njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN RD
HALF MOON BAY AUCKLAND
DEVELOPMENT**

DRAWING TITLE
**TITLE SHEET AND
DRAWING SCHEDULE**

Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	BL
1	20.04.2023	ISSUED FOR RC	BL

Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:250	J00538	001	3



NOTES:

Locations of features approximate only
 Original sheet size A3
 Levels refer to provided survey data



27C WAIPAREIRA AVENUE
 HENDERSON

PH: 027 557 7234
 njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN RD
 HALF MOON BAY AUCKLAND
 DEVELOPMENT**

DRAWING TITLE
SITE PLAN


Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	BL
1	20.04.2023	ISSUED FOR RC	BL


Check all dimensions and levels on site before commencing construction.
 This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:600	J00538	010	3

Type B
 Typical 3.0 - 4.5 m Retaining Height



Type C
 Typical 1.0 - 3.0 m Retaining Height



NOTES:

1, Pile diagrams are indicative only. Refer Sheet 201 and 202 for details.



27C WAIPAREIRA AVENUE
 HENDERSON

PH: 027 557 7234
 njacka@tge.co.nz


PROJECT
**3 PIGEON MOUNTAIN RD
 HALF MOON BAY AUCKLAND
 DEVELOPMENT**

DRAWING TITLE
**NEW RETAINING WALL
 PILE TYPE DIAGRAM**

Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	-
1	20.04.2023	ISSUED FOR RC	BL

Check all dimensions and levels on site before commencing construction. This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.				
PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:250	J00538	100	3



Datum R.L. 0.00

DISTANCE	0.00	TYPICAL 1.0m C/C SPACING	10.00	20.00	30.00	40.00	50.00	60.00	70.00
TOP OF WALL LEVEL	20.34		19.49	19.39	19.29	19.20	17.82	17.51	15.70
TOE OF WALL LEVEL	16.22		16.22	16.28	16.05	15.71	14.55	14.15	12.65
MAX. RETAINED HEIGHT (m) (+550 mm undercut)	3.27		3.27	3.10	3.25	3.48	4.29	4.36	4.06
PILE TYPE	TYPE B PILES								
POLE LENGTH	12.0m								
BASE OF CONCRETE PILE LEVEL	8.34		7.49	7.39	7.29	7.20	5.82	5.51	3.70

NOTES:

- 1, Pile face elevation to be confirmed in detail design stage with detailed survey information and design levels.
- 2, Wall alignment to be confirmed in detail design stage.
- 3, Design top of wall levels from Lot 79 to 86 are 1.0 m lower than the existing timber retaining wall per architecture design.



27C WAIPAREIRA AVENUE
HENDERSON
PH: 027 557 7234
njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN RD
HALF MOON BAY AUCKLAND
DEVELOPMENT**


DRAWING TITLE
**NEW RETAINING WALL
FACE ELEVATION 1**

Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	29.09.2023	ISSUED FOR RFI AND RC	BL
1	20.04.2023	ISSUED FOR RC	BL

Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:250	J00538	101	3



Datum R.L. 0.00		70.00	80.00	90.00	100.00	110.00	120.00	121.00	130.00	133.00
DISTANCE										
TOP OF WALL LEVEL	15.70	14.76	14.24	13.30	11.24	9.99	9.87	/	/	/
TOE OF WALL LEVEL	12.65	11.64	10.14	10.14	9.14	9.14	9.14	/	/	/
MAX. RETAINED HEIGHT (m) (+550 mm undercut)	4.06	4.11	4.09	3.15	2.09	0.85	0.73	/	/	/
PILE TYPE	TYPE B PILES					TYPE C PILES				
POLE LENGTH	12.0m					6.0m				
BASE OF CONCRETE PILE LEVEL	3.70	2.76	2.24	1.30	5.24	3.99	3.87	/	/	/

FACE ELEVATION-2

NOTES:

- 1, Pile face elevations to be confirmed in detail design stage with detailed survey information and design levels.
- 2, Wall alignment to be confirmed in detail design stage.
- 3, Design top of wall levels from Lot 79 - 86 are 1.0 m lower than the existing timber retaining wall per architecture design.



27C WAIPAREIRA AVENUE
HENDERSON
PH: 027 557 7234
njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN RD
HALF MOON BAY AUCKLAND
DEVELOPMENT**

DRAWING TITLE
**NEW RETAINING WALL
FACE ELEVATION 2**

Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	BL
1	20.04.2023	ISSUED FOR RC	BL


Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:250	J00538	102	3

1. MATERIAL PROPERTIES

CONCRETE:	CHARACTERISTIC COMPRESSIVE STRENGTH $f'c = 30 \text{ MPa}$ UNLESS OTHERWISE NOTED.
STEEL UC'S:	GRADE 300 MINIMUM.
TIMBER RAILINGS:	H4 TREATED RADIATA PINE
RAILING FIXINGS:	GALVANISED NAILS
DRAIN COIL:	110mm DIAMETER
GEOFABRIC:	BIDIM A19
DRAINAGE AGGREGATE:	SINGLE/DUAL GRADED (IE. DRAINAGE 40, DRAINAGE 20/40, SGC 25/7) ENCAPSULATED IN BIDIM A19 (OR SIMILAR) FILTER CLOTH OR, SELF FILTERING AGGREGATE (IE. SAP50 EX TAUPO/KAMO)
GALVANISING:	TO AS/NZS4680 GRADE HDG 900

2. MINIMUM CONCRETE COVER TO STEEL POLES IS 75mm WITH A MINIMUM COVER OF 100mm AT THE PILE BASE. THIS WILL REQUIRE EITHER A PACKER OR POURING OF A PUNCH PAD TO ACHIEVE DESIGN.
3. ENDS OF CUT RAILS SHALL BE FLOODED WITH A COPPER NAPHTHENATE TYPE WOOD PRESERVATIVE.
4. THE MAXIMUM RETAINING HEIGHT AND SURCHARGE SLOPE SHALL BE AS SPECIFIED ON THE DESIGN AND SHALL NOT BE EXCEEDED UNLESS APPROVED BY THE DESIGN ENGINEER.
5. THE EXTENT OF EXCAVATION REQUIRED SHALL BE MARKED OUT ON THE GROUND HAVING REGARD TO THE POSITIONS OF POLES, WORKING SPACE FOR CONSTRUCTION, BACKFILL AND DRAINAGE PROVISIONS.
6. A PERFORATED SUBSOIL DRAIN WITH FILTER SOCK SHALL BE LAID AND SURROUNDED IN APPROVED DRAINAGE-GRADED AGGREGATE OR SCORIA WITH INVERT BELOW TOE GROUND LEVELS CONNECTED TO A FREE OUTLET AT A POINT OF SAFE DISCHARGE OR CONNECTED TO STORMWATER SYSTEM.
7. THE CONTRACTOR SHALL REFER TO THE DESIGN ENGINEER AS SOON AS POSSIBLE FOR FURTHER INSTRUCTION SHOULD ANY UNFORESEEN CIRCUMSTANCE OR ABNORMAL SITE CONDITION BE ENCOUNTERED DURING CONSTRUCTION.
8. HORIZONTAL ALIGNMENT OF POLES SHALL VARY BY NO MORE THAN 25mm WHEN PLACING A STRAIGHT-EDGE ACROSS THE FRONT FACE OF THREE CONSECUTIVE POLES.
9. W-BEAM GUARD RAIL TO MEET 'BARRIER PERFORMANCE LEVEL 3' STANDARD CRITERIA AS PER NZTA BRIDGE MANUAL, APPENDIX B.



TYPICAL SECTION 3
SCALE 1:50

TOTAL GROUND ENGINEERING

27C WAIPAREIRA AVENUE
HENDERSON

PH: 027 557 7234
njacka@tge.co.nz

PROJECT

**3 PIGEON MOUNTAIN RD
HALF MOON BAY AUCKLAND
DEVELOPMENT**


DRAWING TITLE

**EXISTING RETAINING WALL
TYPICAL SECTION 3**


Date:	APR 2023		
Cad Ref:	J00538 r2.dwg		
Designed:	BL		
Drawn:	BL		
Checked:	NJ		
Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	-
1	20.04.2023	ISSUED FOR RC	BL


Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	DWG No.	ISSUE
SCALE	1:50	J00538	201	3



Legend:

 DMXX Wall Deflection Monitoring Points

 BSXX Building Settlement Monitoring Points

NOTES:

Locations of features approximate only
Original sheet size A3
Levels refer to provided survey data



27C WAIPAREIRA AVENUE
HENDERSON

PH: 027 557 7234
njacka@tge.co.nz

PROJECT
**3 PIGEON MOUNTAIN RD
HALF MOON BAY AUCKLAND
DEVELOPMENT**

DRAWING TITLE
MONITORING PLAN

Date:	APR 2023
Cad Ref:	J00538 r2.dwg
Designed:	BL
Drawn:	BL
Checked:	NJ

Issue	Date	Issue Description	By
3	12.02.2024	UPDATED AND ISSUED FOR RFI AND RC	BL
3	24.11.2023	ISSUED FOR RFI AND RC	BL
2	30.09.2023	ISSUED FOR RFI AND RC	BL
1	20.04.2023	ISSUED FOR RC	BL

Check all dimensions and levels on site before commencing construction.
This drawing and design remains the property of Total Ground Engineering and may not be reproduced without the written permission of Total Ground Engineering.

PAPER SIZE	A3	JOB No.	J00538	DWG No.	300	ISSUE	3
SCALE	1:600						