

Original sheet size A1 (841x594) Plot Date 2024-03-15 at 3:23:22 PM \corp.pbwan.net\ANZ\ProjectsNZ\5c\5-C4353.54 Weigh Right programme - Bombay Site\Home\04\_CADD\01\_WIP\01\_CAD\5C4353-WSP-54-DR-C-3100.dwg C-3100

8

-20

0-

## NOTES:

- ALL EROSION AND SEDIMENT CONTROL DEVICES ARE TO COMPLY WITH CURRENT NZTA EROSION AND SEDIMENT CONTROL GUIDELINES.
- THIS DRAWING IS FOR CONSENT PURPOSES ONLY.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO DEVELOP A DETAILED EROSION & SEDIMENT CONTROL PLAN.
- ALL TEMPORARY STOCKPILE AREAS AND AREAS OF BARE DISTURBED 3 EARTH THAT WILL REMAIN FOR MORE THAN TWO WEEKS MUST BE GRASSED OR COVERED TO PREVENT EROSION. SHORT TERM STOCKPILES MUST INCLUDE COMPOST FILLED SOCKS AROUND ALL LOW POINTS.
- EROSION AND SEDIMENT CONTROL TO ALSO SPECIFY DUST SUPPRESSION MEASURES.
- THE CONTRACTOR IS TO UNDERTAKE SOIL TESTS TO ASCERTAIN THE MOST APPROPRIATE FLOCCULATION REAGENT FOR USE IN THE CONTROL OF EROSION AND SEDIMENTATION. BENCH TESTS AND THE IMPLEMENTATION OF FLOCCULATION (IF CONFIRMED APPROPRIATE) ARE TO BE INCORPORATED INTO THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL MANAGEMENT AND CARRIED OUT ACCORDING TO SECTION F2.0, COAGULANT AND FLOCCULENT TREATMENT, OF AUCKLAND COUNCIL'S 'GD05' DOCUMENT, EROSION AND SEDIMENT CONTROL GUIDE FOR LAND DISTURBING ACTIVITIES IN THE AUCKLAND REGION JUNE 2016.

## LEGEND:







## 2.

SHEET NO. C-3100

REVISION 0B